

Detailed Estimate for Restoration/Motorable of Road damaged during Flood'2020

GENERAL ABSTRACT OF COST

HEAD FDR DIVISION JAYNAGAR
YEAR 19-20 BLOCK Ladania
NAME OF ROAD: T03 to kabilasa

UNDER CONSTRUCTION

UNDER MAINTENANCE/ OUT OF
MAINTENANCE

Damage length : 68.000

Description	Unit	Quantity	Rate (Rs.)	Amount (Rs.)
Providing and filling brick bats in ditches including cost of brick bats and labour all complete job as per specification and direction of E/I.	Cum	219.806	1867.76	410545.00
		231.01		431464.00
			Total =	410545.00
			Add GST @ 12%	492654.00
		219.806	Add L.Cess @ 1%	4105.00
Add Seignorage Fee	231.01 m ³	x Rs. 1063.00	x 10.0%	23365.00
			Grand Total =	512111.00

Grand Total= 487280.00

Five Lacs Twelve Thousand One Hundred and Eleven only.

Rs 487280.00

कार्यालय जयनगर राउन्ड रोड कोटि रोड परियोजना के अंतर्गत कार्य का प्रमाणित किया जाता है कि राशि 336 हजार दिनांक 12-04-2021 ई. के अनुसार समीक्षा और प्रमाणित की जा चुकी है।

Post fec to T/A for Rs 487280.00 (Rupees four Lacs Eighty Seven thousand two hundred Eighty) only.

26/11/20

J.E

Works division Jaynagar

26/11/20

A.E

Works division Jaynagar

Superintending Engineer

RWD, Works Circle, Garbhanga

12/04/2021

26/11/20

E.E

Works division Jaynagar

Detailed Estimate for Restoration/Motorable of Road damaged during Flood'2020

HEAD

FDR

NAME OF ROAD :

T03 to kabilasa

LENGTH OF ROAD

3.52 km

BLOCK :

Ladania

Damage length :

68.00

DIVISION : JAYNAGAR

CIRCLE : DARBHANGA

Measurement Brick bat

CH	Nos	Length	Width			Avg Width	Depth			Avg Dept	Qty (cum)	
1290	1	7	3	3.75	0	3.38	0.5	0.45	0	0.48	11.222	
1820	1	6	3.25	2.5	0	2.88	0.6	0.75	0	0.68	11.644	
2220 to 2300	1	10	1.5	0.9	1.25	1.22	0.6	0.5	0	0.55	6.692	
2220 to 2300	1	10	1.25	1	1.5	1.25	0.75	1	1.2	0.98	12.292	
3000	1	35	2	1.9	2.5	2.13	2.5	2.75	2.1	2.33	189.156	177.956
Total Qty											231.006	219.806

Chaudhary
25/11/20

J.E

S. S. S.
26/11/20
A.E

J. J. J.
26/11/20
E.E