

Detailed Estimate for Restoration/Motorable of Road damaged
during Flood'2020

Block : Babubarhi

Division : Jaynagar

Circle : Darbhanga

ABSTRACT OF COST


Name of Road : PWD Road to Murhadi Balati Tol

Length of Road : 1.050 Km

Estd. Length : 16 Mtr.

Sl. NO.	Item of Works	Unit	Quantity	Rate	Amount (Rs.)
1-	Providing and filling brick bats in ditches including cost of brick bats and labour all complete job as per specification and direction of E/I.	CUM	72.75	1867.76	135880.00
				Total Rs.	135880.00
				Add GST @ 12%	16306.00
				Add L.Cess @ 1%	1359.00
	Add Seignorage Fee		72.75 m ³ x Rs. 1063.00 x 10 %		7733.00
				Grand Total Rs.	161278.00

Say ₹ 1,61,300.00
161278.00



Junior Engineer
Babubarhi


Assistant Engineer
Babubarhi


Executive Engineer
RWD Work Division,
Jaynagar.

कार्यपालक अभियन्ता द्वारा कांफि कार्य नगरेल गेमा खुर् का पनफे 336 अगु दिनेक 12.04.2021
के हस समीपन जॉय नालेवेदन के आधार पर —

Post-recto T/A for Rs 161278.00 (Rupees one lac sixty one thousand two hundred seventy eight) only.


Superintending Engineer
RWD, Works Circle, Darbhanga
12/04/2021

**Detailed Estimate for Restoration/Motorable of Road damaged
during Flood'2020**

Name of Road : PWD Road to Murhadi Balati Tol

Length of Road : 1.050 KM

Estd. Length : 16 Mtr.

Block : Babubarhi

Division : Jaynagar

Circle : Darbhanga

S.N.	ITEM OF WORKS	MEASUREMENT (L x B x H/D)	QUANTITY
1-	Providing and laying Brick Bats including -- do -- do -- E/I.		
	CH- 0.400 to 0.500 Km	1 x 3.00 x 1/2(3.75 + 5.75) x 1/2(0.55 + 0.75) =	9.26 m ³ ✓
		1 x 10.00 x 1/2(4.50 + 6.75) x 1/2(0.60 + 1.40) =	56.25 ✓
		1 x 3.00 x 1/2(3.75 + 5.90) x 1/2(0.60 + 0.40) =	7.24 ✓
		Total	72.75 m³ ✓


Junior Engineer
Babubarhi


Assistant Engineer
Babubarhi


Executive Engineer
RWD Work Division,
Jaynagar.