

Detailed Estimate for Restoration/Motorable of Road damaged during Flood'2020

GENERAL ABSTRACT OF COST

HEAD FDR DIVISION JAYNAGAR
YEAR 19-20 BLOCK Basopatti
NAME OF ROAD : CHILMILIYA PMGSY TO UTTARWARI TOL SIRIYAPUR

UNDER CONSTRUCTION

UNDER MAINTENANCE/ OUT OF
MAINTENANCE

Damage length :

95.75m ~~25.000~~

Description	Unit	Quantity	Rate (Rs.)	Amount (Rs.)
Providing and filling brick bats in ditches including cost of brick bats and labour all complete job as per specification and direction of E/I.	Cum	55.39	1867.76	103457.00
			Total =	103457.00
			Add GST @ 12%	12415.00
			Add L.Cess @ 1%	1035.00
Add Seignorage Fee	55.39 m ³	x Rs. 1063.00	x 10.0%	5888.00
			Grand Total =	₹ 1,22,795

Grand Total= 122795.00

One Lac Twenty Two Thousand Seven Hundred and Ninty Five only.

कार्यपालक अभियन्ता या का. वि. कार्यप्रमंडल जयनगर का पत्रांक - 336 अगु दिनांक 12-4-2021 के द्वारा
अप्रति जौ च प्रविष्ट के अकारपुर -

Post-Recd 1/A for Rs 1,22,795 = (Rupees) One Lac & twenty two
thousand Seven hundred Ninety five) only.

Superintending Engineer

RWD, Works Circle, Darbhanga

13/04/2021

J.E

A.E

E.E

Works division Jaynagar

Works division Jaynagar

Works division Jaynagar

Detailed Estimate for Restoration/Motorable of Road damaged during Flood'2020

HEAD

FDR

NAME OF ROAD :

CHILMILIYA PMGSY TO UTTARWARI TOL SIRIYAPUR

LENGTH OF ROAD

4.32 km

BLOCK :

Basopatti

DIVISION : JAYNAGAR

Damage length :

~~25.00~~ 95.95m

CIRCLE : DARBHANGA

Measurement Brick bat

CH	Nos	Length	Width			Avg Width	Depth			Avg Depth	Qty (cum)	
2600	1	25	0.5	0.5	0.5	0.48	1	0.8	0	0.875	10.573	✓
2700 TO 2750	1	24	0.6	0	0	0.6	1.2	0.6	0	0.9	12.96	✓
2700 TO 2750	1	7	0.5	0.6	0	0.55	0.5	0.3	0	0.4	1.54	✓
2700 TO 2750	1	6	1.2	1.1	0	1.15	1.1	1	0	1.05	7.245	✓
2900 TO 2950	1	20	1	1.2	0	1.1	0.8	0.9	0	0.85	18.7	✓
3200	1	3.75	1	0.9	0	0.95	0.3	0	0	0.25	0.891	✓
3400	1	2.5	1	0.85	0.9	0.92	0.3	0.3	0.4	0.3	0.688	✓
3450	1	1.5	0.7	0.75	0	0.73	0.3	0.3	0.4	0.3	0.326	✓
3550 TO 3600	1	1	0.5	0.6	0	0.55	0.3	0.3	0.4	0.3	0.165	✓
3550 TO 3600	1	2	0.7	0.75	0	0.73	0.3	0.3	0.4	0.3	0.435	✓
3850	1	3	2	2.15	0	2.08	0.3	0.3	0.4	0.3	1.868	✓
Total Qty											55.391	✓


25/12/2020

J.E


25/12/2020
A.E



E.E