

Detailed Estimate for Restoration/Motorable of Road damaged during Flood/2020

GENERAL ABSTRACT OF COST

HEAD FDR DIVISION JAYNAGAR
YEAR 19-20 BLOCK Jaynagar LADANJA
NAME OF ROAD : PANCHAYAT SIDHAPKALA VILLAGE YOGIYA AGHORI DAS HOUSE TO DHAURI RIVER

UNDER CONSTRUCTION

UNDER MAINTENANCE/ OUT OF MAINTENANCE

Damage length :

74.000

Description	Unit	Quantity	Rate (Rs.)	Amount (Rs.)
Providing and filling brick bats in ditches including cost of brick bats and labour all complete job as per specification and direction of E.I.	Cum	170.263 181.91	1867.76	318010.20 339762.00
			Total =	318010.20 339762.00
			Add GST @ 12%	38161.04 40777.00
			Add L.Cess @ 1%	3180.10 3398.00
Add Seignorage Fee	170.263 181.91 m ³	x Rs. 1063.00	x 10.0%	18099.40 19337.00
			Grand Total =	2403268

Grand Total = 2403268.00

Four Lacs Three Thousand Two Hundred and Sixty Eight only.

पंचायत समिति आचार्य कार्यालय, जयनगर, पंचायत 336 मीटर दिनांक 12.04.2021

Post facto T/A for Rs 3976500.00 (Three lacs Ninety Seven thousand four hundred and fifty) only -

Superintending Engineer

RWD, Works Circle, Darbhanga

26/12/20

26/12/20

26/12/20

26/12/20

J.E

A.E

E.E

Works division Jaynagar

Works division Jaynagar

Works division Jaynagar

Detailed Estimate for Restoration/Motorable of Road damaged during Flood'2020

HEAD

FDR

NAME OF ROAD :

PANCHAYAT SIDHAPKALA VILLAGE YOGIYA AGHORI DAS HOUSE TO DHA

LENGTH OF ROAD

3.38 km

BLOCK :

Jaynagar

DIVISION : JAYNAGAR

Damage length :

74.00

CIRCLE : DARBHANGA

Measurement Brick bat

CH	Nos	Length	Width			Avg Width	Depth			Avg Dept	Qty (cum)	
510	1	9	3.5	5.5	0	4.5	1.5	1.25	1.8	1.52	61.425	20
550	1	30	3.5	2.65	0	3.075	0.9	0.6	0.45	0.65	59.963	
570	1	35	2.65	1.5	0	2.075	0.9	0.6	1	0.83	60.521	58.10
Total Qty											181.909	

170-263 m

Chauhan
26/12/20

J.E

Sgt
26/12/20

A.E

J
26/12/20

E.E