

Detailed Estimate for Restoration/Motorable of Road damaged during Flood'2020

GENERAL ABSTRACT OF COST

HEAD FDR DIVISION JAYNAGAR
YEAR 19-20 BLOCK Basopatti
NAME OF ROAD : Purnahi Chauk to Mehatter Patti Tol Baira Tak

UNDER CONSTRUCTION

UNDER MAINTENANCE/ OUT OF
MAINTENANCE

Damage length : 42.000

Description	Unit	Quantity	Rate (Rs.)	Amount (Rs.)
Providing and filling brick bats in ditches including cost of brick bats and labour all complete job as per specification and direction of E/I.	Cum	105.231 107.38	1867.76	196546.20 200551.00
			Total =	196546.20 200551.00
			Add GST @ 12%	23586.52 24066.00
			Add L.Cess @ 1%	1965.46 2006.00
Add Seignorage Fee		105.231 107.38 m ³	x Rs. 1063.00 x 10.0%	1186.20 1144.00
			Grand Total =	233283.20 238037.00

Grand Total= 233283.20
238037.00

Two Laes Thirty Eight Thousand and Thirty Seven only.

कार्यपालक अभियन्ता झा काठवि कारभ नगल मेरगापुर के पत्रके 336 अनु दिनांक 12.04.2021

के डर। समर्पित अन्य प्रतिवेदन के आधार पर

Post-facto T/A for Rs 233283.20 (Rupees two laes thirty three thousand - two hundred eighty three) only.

13-04-21

Superintending Engineer
RWD, Works Circle, Darbhanga

13/04/2021

25/12/2020
J.E

Works division Jaynagar

25/12/2020
A.E

Works division Jaynagar

26/12/2020

E.E

Works division Jaynagar

Detailed Estimate for Restoration/Motorable of Road damaged during Flood'2020

HEAD	FDR	
NAME OF ROAD :	Purnahi Chauk to Mehatter Patti Tol Baira Tak	
LENGTH OF ROAD	1.73 km	
BLOCK :	Basopatti	DIVISION : JAYNAGAR
Damage length :	42.00	CIRCLE : DARBHANGA

Measurement Brick bat

CH	Nos	Length	Width			Avg Width	Depth			Avg Depth	Qty (cum)	
1000 TO 1100	1	4.5	3.5	3.6	3.5	3.53	0.3	0.6	0.5	0.467	7.42	
1000 TO 1100	1	9	4.5	4	4.3	4.27	0.6	0.5	0.5	0.517	19.84	
1200	1	9	3.6	3.5	3.8	3.62	1	1.3 1.4	1.3 1.3	1.233 1.3	42.315 40.171	
1300 TO 1400	1	6	3	0	0	3	0.3	0.5	0.5	0.417	7.5	
1300 TO 1400	1	7.5	4.5	4.2	4.3	4.33	0.6	0.5	0.7	0.6	19.5	
1300 TO 1400	1	6	3	0	0	3	0.6	0.6	0	0.6	10.8	
Total Qty											107.375	
105.231 m ³												


25/12/2020
J.E


25/12/2020
A.E


E.E