

Detailed Estimate for Restoration/Motorable of Road damaged during Flood/2020

GENERAL ABSTRACT OF COST

HEAD FDR
YEAR 19-20
NAME OF ROAD : Kariyappati-T04(SH)

DIVISION
BLOCK

JAYNAGAR
Basopatti

UNDER CONSTRUCTION

UNDER MAINTENANCE/ OUT OF
MAINTENANCE

Damage length :

67.000

Description	Unit	Quantity	Rate (Rs.)	Amount (Rs.)
Providing and filling brick bats in ditches including cost of brick bats and labour all complete job as per specification and direction of E/I.	Cum	65.94	1867.76	123166.00
			Total =	123166.00
			Add GST @ 12%	14779.92
			Add L.Cess @ 1%	1232.00
Add Seignorage Fee	65.94 m ³	x Rs. 1063.00	x 10.0%	7009.10
			Grand Total =	146188.00

Grand Total=

146188.00

One Lac Fourty Six Thousand One Hundred and Eighty Eight only.

Rs 146188.00

कार्यपालक अभियन्ता द्वारा कां विन कार्य प्रमोड अभियन्ता का पत्रिके 336 मनु दिनांक - 12-04-2021
के द्वारा समीक्षा अंतर्गत अतिरिक्त के आधार पर -

Post-Facto T/A for Rs 146188.00 (Rupees one lac forty six thousand one hundred eighty) only.

Superintending Engineer
RWD, Works Circle, Darbhanga

J.E

A.E

E.E

Works division Jaynagar

Works division Jaynagar

Works division Jaynagar

Detailed Estimate for Restoration/Motorable of Road damaged during Flood'2020

READ

FDR

NAME OF ROAD :

Kariyappati-T04(SH)

LENGTH OF ROAD

3.20 km

BLOCK :

Basopatti

DIVISION : JAYNAGAR

Damage length :

67.00

CIRCLE : DARBHANGA

Measurement Brick bat

CH	Nos	Length	Width			Avg Width	Depth			Avg Depth	Qty (cum)	
2700	1	67	3.5	3.6	3.2	3.43	0.3	0.3	0.3	0.287	65.943	✓
Total Qty											65.943	✓


J.E


25/12/2020
A.E


E.E