

FDR

DISTRICT :- DARBHANGA

BLOCK :- BAHERI


Name of Raad :- REO Road to Bhagwatol

Length of the Road:- 2.100 KM


Effective Length 0.186 KM.

GENERAL ABSTRACT OF COST

No.	Item of Work	Amount (in Rs.)
1	Cost for restoration	3,88,236.33 154738.31
2	Add 12 % GST	46,588.36 18568.59
3	Add Seigniorage	-22,095.73 8806.63
4	Add 1 % Labour Cess	-3,882.36 1547.38
Total cost:-		4,60,802.78 183660.91



14.12.2020
Junior Engineer
Baheri


15/12/2020
Assistant Engineer
Baheri


Executive Engineer
R.W.D.(W) Division, Darbhanga-1

आयुक्तिक समिति, ग्रां का वि, आयुक्तिक-प्रमाण का पता: 542 3130
दिनांक: 07/04/2021 के द्वारा समिति जीव प्रविर्दन के आधुन पर

Post-facto T/A for Rs. 183661=00 (Rupees one lac eighty three thousand six hundred sixty one) only



09.04.21
Superintending Engineer
RWD, Works Circle, Darbhanga
09/04/2021


Detailed estimate for making moterable road.

Road :- REO Road to Bhagwatol
 BAHARI
 DISTRICT :- DARBHANGA
 R.W.D. Works Division Darbhanga-1

No.	Item	Unit	No.	Length (m)	Avg. Breadth (m)	Avg. Depth / Height	Quantity	Rate	Amount
1	Labour and placing of brick bats with light ramming including cost of brick bats by tractor	cum	From REO Road						
			0.000 KM to 1.000 KM.						
			1	10.00	3.00	0.500	15.000		
			1	16.00	1.0 2.40	1.850	71.040	29.600	
			1	14.00	1.0 2.50	0.600	21.000	8.400	
			1	5.00	1.0 2.00	0.450	4.500	2.250	
			1	12.00	1.0 2.40	0.500	14.400	6.000	
			1	22.00	1.0 2.40	0.250	13.200	5.500	
			1	11.50	1.0 2.00	0.225	5.175	2.587	
			1	8.00	1.0 2.20	0.200	3.520	1.600	
			1	10.00	0.90 1.95	0.650	12.675	5.850	
			1	12.00	1.0 2.20	0.230	6.072	2.760	
			2	15.00	1.0 2.00	0.200	12.000	3.000	
			1	15.00	1.0 4.60	0.220	5.280	3.300	
			1	20.00	1.0 2.00	0.600	24.000	12.000	
							82.847		
							Total	207.862	1867.78

388236.33
 154738.31
 388236.33


 14.12.2020
 Junior Engineer
 Baheri


 15/12/2020
 Assistant Engineer
 Baheri


 Executive Engineer
 R.W.D.(W) Division, Darbhanga-1