

FDR

DISTRICT :- DARBHANGA

BLOCK :- BAHERI

Name of Road :- NARBANDH TO ATAHAR GOD TOL

Length of the Road:- 0.860 KM.

Effective Length 0.860 KM.

GENERAL ABSTRACT OF COST

No.	Item of Work	Amount (in Rs.)
1	Cost for restoration	8,36,709.79
2	Add 12 % GST	1,00,405.17
3	Add Seigniorage	47,619.74
4	Add 1 % Labour Cess	8,367.10
Total cost:-		9,93,101.80

Junior Engineer
Baheri

Assistant Engineer
Baheri

Executive Engineer
R.W.D.(W) Division, Darbhanga-1

कार्यपालक अभियंता द्वारा कार विर काम प्रमंडल-कुलपएर के फाईक 542 अनु
दिनांक 07/04/2021 / के द्वारा स्माईल ऑन-य प्रतिवेदन के आयाल पर।
Post-Facto T/A for Rs-9,93,102 = W (Rupees Nine lacs -
Ninety three thousand one hundred two) only.

Superintending Engineer

RWD, Works Circle, Darbhanga
09/04/2021

Detailed estimate for making moterable road.

Road - NARBANDH TO ATAHAR GOD TOL.
BAHERI
DARBHANGA
Division Darbhanga 1

Item	Unit	No	Length (m)	Breadth (m)	Depth Height (m)	Quantity	Rate	Amount	
Laying and placing of brick bats including cost of bats by tractor	cum	From Narbandh 0.000 KM to 0.860 KM.							
		1	15.00	3.70	0.600	33.300	✓		
		1	30.00	3.70	0.600	66.600	✓		
		1	30.00	4.10	0.700	86.100	✓		
		1	30.00	3.70	0.600	66.600	✓		
		1	15.00	3.30	0.400	19.800	✓		
		1	18.00	3.50	0.500	31.500	✓		
		1	30.00	3.30	0.600	59.400	✓		
		1	25.00	2.30	0.450	25.875	✓		
		1	28.00	3.50	0.600	56.800	✓		
						Total	447.975	186	838.125

Engineer
Baheri

Assistant Engineer
Baheri

Executive Engineer
Road & T.W. Division Darbhanga 1