

Detailed Estimate for Restoration/Motorable of Road damaged during Flood/2020

HEAD

FDR

GENERAL ABSTRACT OF COST

YEAR

19-20

DIVISION

JAYNAGAR

NAME OF ROAD : Tanuahi to Boraha

BLOCK

Ladania

UNDER CONSTRUCTION

UNDER MAINTENANCE/ OUT OF MAINTENANCE

Dredge length :

65.000

Description	Unit	Quantity	Rate (Rs.)	Amount (Rs.)
Providing and filling brick bats in ditches including cost of brick bats and labour all complete job as per specification and direction of E/I.	Cum	437.796 467.66	1867.76	817698.20 873480.00
			Total =	817698.20 873480.00
			Add GST @ 12%	98124.78 104181.00
			Add L.Cess @ 1%	8177.20 8735.00
Add Seignorage Fee	437.796 467.66 m ³	x Rs. 1063.00	x 10.0%	46538.49 49712.00
			Grand Total =	₹ 10,36,745

Grand Total = 970537.20
1036745.00

Ten Lacs Thirty Six Thousand Seven Hundred and Fourty Five only.

कार्यपालक इन्जिनियर आरका वि० कार्यप्रमाण मन्त्रालय का पत्रांक 336 अगस्त 12.04.2024 के द्वारा स्वीकृत और जारी किया गया है।

Post - Recd T/A for Rs 970537.20 (Rupees Nine lac Seventy thousand five hundred thirty seven) only.

Superintending Engineer
RWA, Works Circle, Darbhanga

26/12/20

J.E

ks division Jaynagar

26/12/2024

A.E

Works division Jaynagar

26/12

E.E

Works division Jaynagar

Detailed Estimate for Restoration/Motorable of Road damaged during Flood'2020

HEAD	FDR	
NAME OF ROAD :	Tanuahi to Boraha	
LENGTH OF ROAD	3.38 km	
BLOCK :	Ladania	DIVISION : JAYNAGAR
Damage length :	65.00	CIRCLE : DARBHANGA

Measurement Brick bat

CH	Nos	Length	Width			Avg Width	Depth			Avg Dept	Qty (cum)	
1830	1	51	1.8	4.5	3.5	3.27	2.1	2.4	2.5	2.33	388.733	358.866
1890	1	14	2.1	3.5	3	2.87	1.8	2	2.1	1.97	78.929	
Total Qty											467.662	

437.796 m)

Chandray
26/12/20

J.E

Voluno
A.E

26/12/20
E.E