

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

CIRCLE – R.W.D Works Circle, Chapra

DIVISION – R.W.D Works Division, Marhaura

Name of Work – Motorable of Road from Salakhua
Marhaura PMGSY path se Harijan Tola tak

Block - Amnaur

Estimated Cost – Rs 760075.00

2020-21

ABSTRACT OF COST

Inspection Report for Flood damage work

Date:

1. Name of PIUs- E.E. RWD (W.D.) Moradabad

2. Name of Block/Road- Amnara - Seelakher, Moradabad, P.H. 651, P.O. 651
Dargi, Tola

A. For Road

1. Damage Location/Chainage : 05, 32, 124 H.

2. Damage Length : 76.50 Y.

3. Nature of Damage : Road cutting due to flood.

4. Details of Restoration :

i Material being used in Restoration : Bridge material used for abutments

ii Equipment/Tools being used in Restoration works: Roller, Trencher, etc. etc.

iii Procedure taken up in Restoration works : Applying, etc. etc.

iv Restored Length : 76.50

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :


4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :


Signature of JE/AE/EE

4/12/20




Signature
Er. Akhilesh Kumar
(Name of Inspector)
EE
RWD (W.D.) Division
SONEPUR.

प्रतिवेदन

कार्य का नाम :- सारण के सड़क पथ को PMGSY/MMGSY/GTSNY/NABARD से
शीर्ष :- FDR
प्राक्कलित राशि :- 760075/-
प्रखण्ड का नाम :- अमनौर

जिला-सारण।

प्रस्तुत प्राक्कलन शीर्ष PMGSY/MMGSY/GTSNY/NABARD/MR-3054 अर्तगत निर्मित/निर्माणाधीन पथ के गत महीने में इस जिला में आये बाढ़/अतिवृष्टि के कारण क्षतिग्रस्त हुए पथों को चलने लायक (Motarable) बनाने हेतु विभागीय दिशा-निर्देशानुसार कार्यपालक अभियंता, ग्रा0का0वि0, कार्य प्रमंडल मढ़ौरा के दिशा-निर्देशन में कुल रु0-760075/- के लिए तैयार किया गया है।

आवश्यकतानुसार तत्काल प्रभाव से पथों को चलने लायक बनाने हेतु प्राक्कलन में Bricks Bats, Sand Bag, Hume-Pipe इत्यादी का प्रावधान आवश्यक लम्बाई, चौड़ाई एवं मोटाई में प्राक्कलन के अनुसार प्रावधान किया गया है।

योजना एवं कार्य की महत्ता के साथ-साथ जनहित के लिए अतिउपयोगी प्राक्कलन को कार्यहित में स्वीकृति हेतु प्रस्तुत किया जा रहा है।

04/12/2020
1st Am

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, मढ़ौरा।

साधन

Name of Work – Motorable of Road from Salakhua
Marhaura PMGSY path se Harijan Tola tak


Block – Amnaur

Sl No.	Particulars	Amount(In Rs)
A	Cost of Restoration Work	Rs 672633
B	Add 12% GST on (A)	Rs 80716
C	Add 1% L.Cess on (A)	Rs 6726
	Total Cost	Rs 760075


J.E.

RWD

Amnaur


A.E.

RWD

Amnaur


E.E.

RWD

Marhaura


T/A for Rs 760,075 = 00 (Rupees Seven lac seventy-
thousand seventyfive) only.



अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, छपरा


Detailed Estimate

Name of Work - Motorable of Road from Salakhua Marhaura PMGSY path se Harijan Tola tak

Sl.No.	Item	S No	Length	Width	Avg.H/D	Qnty	Unit	Rate	Amount
1	Providing laying and spreading brick bats in road ditches all complete as per approved design, specification and direction of E/I.	1	14.5	3.9	1.25	70.69			
		2	28	4.05	1.2	136.08			
		2	34	4.05	1	137.70			
		Total					344.47	Cum	1909.87
2	Filling and spreading local sand over brick bats as per drawing and technical specification Clause 303.5.9	1	14.5	3.9	0.1	5.66	0		
			28	4.05	0.1	11.34			
		2	34	4.05	0.1	13.77			
		Total					30.77	Cum	479.27
TOTAL									672633


J.E. 04/12/20
RWD
Amnaur


A.E.
RWD
Amnaur


E.E.
RWD
Marhaura