


# RURAL WORKS DEPARTMENT



## GOVERNMENT OF BIHAR

NAME OF ROAD:- SIMARBANNI DHARMANAND MANDAL TO  
GANGA RISHIDEV TOLA

DIVISION:- R.W.D, WORKS DIVISION, FORBESGANJ

CIRCLE:- R.W.D, WORK CIRCLE, KISHANGANJ

BLOCK:- FORBESGANJ

### ESTIMATED COST

999438.00

Inspection Report for flood damage work

Date:

1. Name of PIUs- RWD WORK DIVISION Furberga

2. Name of Block/Road- Bhargama / Simar bari alhamra mau mandal to  
Changa Rikher dola

A. For Road

1. Damage Location/Chainage :

2. Damage Length :

30 m

3. Nature of Damage :

side cutting

4. Details of Restoration :

i Material being used in Restoration

: local sand, B/Bat, Baulso

ii Equipment/Tools being used in Restoration works:

pile, cc bags

iii Procedure taken up in Restoration works

Tractor, TCB, labor

iv Restored Length

30 m

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

NA

Sign





Signature

(Name of Inspector)

# Abstract of Cost

**Name of Work :** Estimate for Repairing/Restoration/Making Motorable Roads Damaged during flood in 2020 in ARARIA District

**Name of Road:**

**SIMARBANNI DHARMANAND Mandal TO GANGA RISHIDEV TOLA**  
District: ARARIA

**Block:** BHARGAMA

**Division :** RWD, Works Division, FORBESGANJ

**Circle:** RWD, Work Circle, KISHANGANJ

Sl No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	435.00	627.77	273079.95
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	696.00	75.86	52798.56
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	174.00	40.06	6970.44
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
		Per Bags	12801.69	37.35	478143.03
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				
		Cum	43.50	1870.43	81363.71
TOTAL AMOUNT =					892355.68
ADD 12.00 %GST=					107082.68
SAY TOTAL AMOUNT =					999438.37

999438.00

*[Signature]*  
JE  
17/06/2020

AE  
RWD SUB DIV.  
FORBESGANJ

EE  
RWD WORKS DIV. FORBESGANJ

RWD SUB DIVISION-FORBESGANJ

*Technically Approved Rs. 999438.00 (Nine lakhs ninety nine thousand  
four hundred thirty eight only)*

*[Signature]*  
KISHANGANJ  
20/6/20




## Detailed Estimate

me of Road:

### SIMARBANNI DHARMANAND MANDAL TO GANGA RISHIDEV TOLA

No.	Items of Works	Nos.	L (m)	B (m)	D (m) IN (Av.)	Quantity (m <sup>3</sup> )
	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.					
	SIDE CUTTING NEAR CULVERT	2	29.00	(2.50+3.50)/2	(3.00+2.00)/2	435.00
					TOTAL=	435.00
					Total Qty =	435.00
	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.					
	SIDE CUTTING NEAR CULVERT	2	29.00	3.00	4.00	696.00
					Total Qty =	696.00
	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.					
	SIDE CUTTING NEAR CULVERT	2	29.00	3.00		174.00
					Total Qty =	174.00
	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.					
	SIDE CUTTING NEAR CULVERT	2	29.00	(3.00+2.00)/2	(3.00+2.00)/2	362.50
					TOTAL=	362.50
					Total No. of EC Bags =(234.67X35.315)	12801.69
					SAY NO OF BAGE=	12802
	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.					
	SIDE CUTTING NEAR CULVERT	2	29.00	(3.00+2.00)/2	0.30	43.50
					Total Qty. =	43.50

  
 JE

AE

EE

RWD SUB DIV- FORBESGANJ

RWD SUB DIV. FORBESGANJ

RWD WORKS DIV. FORBESGANJ