



GOVERNMENT OF BIHAR

NAME OF WORK :- Restoration work of Road from S061 to
bhagat tola (chako chhapra)

(FDR PART-A)

Restoration Length :- 0.7 km

Block:- mushahari

DETAILED PROJECT REPORT

UNDER FDR (2245)

ESTIMATED COST

Rs. 1,236,900.00

-: PREPARED BY :-
EXECUTIVE ENGINEER
R.W.D. (W) DIVISION
MUZAFFARPUR EAST 1

Inspection Report for Flood Damage Work

Date

1 Name of PUC - P.E. Road, Mynaharipur Cent - I
2 Name of Block/Road - Mynaharipur / Restoration work of Road from
SOGI to bhagat tola (Chako Chakra)

A For Road

1 Damage Location/Chainage At onyong Place

2 Damage Length 211 mtr

3 Nature of Damage Complete traffic block due to breach of
road

4 Details of Restoration Works-

i Material being used in Restoration Works - Bitumen

ii Equipments/Tools being used in Restoration Works - Roller, Tractor, JCB
Nagap

iii Procedure Taken up in Restoration Works - Immediate traffic

iv Restored Length 211 mtr Restoration

B. For Bridge

1 Damage Location/Chainage

2 Damage Length

3 Nature of Damage

4 Details of Restoration Works-

i Material being used in Restoration Works-

ii Equipments/Tools being used in Restoration Works-

iii Procedure Taken up in Restoration Works-

iv Restored Length

N/A

Signature of JE/ AE/ EE

Signature

(Name of Inspector)

प्रतिवेदन

कार्य का नाम Restoration works of Road from
Sobai to Bhagat to/a (Chakra) ^{Chakra} पथ में अप्रत्याशित बाढ़/अतिवृष्टि: 2020 से क्षतिग्रस्त पथ में
कामायात धालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रमुख Saxena
क्रिय वर्ष 2020-2021
प्राक्कलित राशि - Rs 12,36,900.00

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 12,36,900.00 है,

प्रमुख Saxena में यातायात बहाली हेतु आपातकालीन मरम्मत के
लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521 दिनांक 05.08.2020 द्वारा
दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में Bitum Work, मरकर पथ को धालू
करने का प्रावधान किया गया है। प्राक्कलन वर्तमान दल अनुसूचित दर पर तैयार किया गया है। इसका
वर्तमान स्वीकृति अंशित है।

Kumar

कनिष्ठ अभियंता

12.12.2020

सहायक अभियंता,

12-12-20

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल मुजफ्फर
पूर्व-1

NAME OF WORK:- Restoration work of Road from S061 to bhagat tola (chako chhapra)

Total Length :-

1.23

Restoration Length :- 0.4

ABSTRACT OF COST

Sl. No.		Unit	Rates	Quantity	Amount
1	<u>Providing and Laying of Brick Bats:</u> Placing tractor at loading point loading with front end loader dumpong, turning for return trip exluding time for haulage and return tirp	Cum	1,768.60	588.95	1,041,617.00
2	Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I.	Rm	49.40	-	-
3	Providing including labour for filling empty cement bag with local sand, stiching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I	Nos	36.20	-	-
Total Amount					Rs. 1,041,617.00
Add for GST @ 12%					Rs. 124,994.00
Add for Labour Cess @ 1%					Rs. 10,416.00
Add for Seigniorage Fee					Rs. 59,896.00
Gross Total Amount					Rs. 1,236,923.00
Say					Rs. 1,236,900.00

Anil Kumar
J.E. 12/12/2020

[Signature]
12.12.2020
A.E

RWD, Sub-Division, Saraiya

[Signature]
12.12.20
Executive Engineer
RWD(W) Div. Muzaffarpur East 1

Technically approved for Rs. 1236900.00 (Rs. Twelve lacs thirty six thousand nine hundred) only

[Signature]
27/12/20 SEI RWD
Muzaffarpur