

FDR

DISTRICT :- DARBHANGA

BLOCK :- BAHERI


Name of Raad :- MAHULICHOWK TO CHAKLA PART -B

Length of the Road:- 8.926 KM


Effective Length 0.823 KM.

GENERAL ABSTRACT OF COST


Sl No.	Item of Work	Amount (in Rs.)
1	Cost for restoration	20,54,278.25 1995494.23
2	Add 12 % GST	2,46,513.39 239459.30
3	Add Seigniorage	1,16,915.33 113569.75
4	Add 1 % Labour Cess	20,542.78 19954.94
	Total cost:-	24,38,249.75 2368478.22


14.12.2020
Junior Engineer
BAHERI


18/12/20
Assistant Engineer
BAHERI


Executive Engineer
R.W.D.(W) Division, Darbhanga-1

आविष्टान समिति, ज्ञात जा कि, आविष्टान फलपत्र का प्राप्ति: 542 अ.रु.
दिनांक: 07/04/2021 के द्वारा समिति जौंच प्रतिवेदन के आधार पर -
Post- facto T/A for Rs 23,68,478/- (Rupees Twenty three-
Lacs) sixty eight thousand four hundred seventy eight) only.


09.04.21
Superintending Engineer
RWD, Works Circle, Darbhanga
09/04/2021

Detailed estimate for making moterable road.

Name of Raad :- MAHULICHOWK TO CHAKLA
BLOCK :- BAHERI
DISTRICT :- DARBHANGA
R.W.D. Works Division Darbhanga-1

Sl. No.	Item	Unit	No.	Length (m)	Avg. Breadth (m)	Avg. Depth / Height	Quantity	Rate	Amount
1	Labour and placing of brick bats with light raming including cost of brick bats by tractor	cum	From Mahulichowk						
			2.000 KM to 3.000 KM.						
			1	2.00	1.50	0.450	1.350		
			1	12.00	1.30	0.450	7.020		
			1	9.00	1.50	0.500	6.750		
			1	30.00	3.20	0.433	41.568		
			1	30.00	3.40	0.445	45.390		
			2	30.00	3.40	0.450	93.150	91.80	
			1	4.00	3.65	0.450	6.570		
			1	30.00	3.70	0.500	55.500		
			1	10.90	2.00	0.390	8.502		
			2	30.00	3.70	0.450	90.450	79.20	
			2	30.00	3.34	0.420	84.168		
			1	30.00	3.70	0.410	45.510		
			1	14.00	3.70	0.400	20.720		
			1	12.00	2.10	0.300	7.560		
			1	25.00	2.80	0.280	19.600		
			1	4.00	2.60	0.250	2.600		
			1	16.00	3.20	0.480	24.576		
			1	7.00	3.40	0.390	8.463	7.35	
			4.000 KM to 5.000 KM						
			1	30.00	3.40	0.200	20.400		
			1	22.00	3.30	0.180	13.068		
			1	7.50	1.20	0.220	1.980		
			1	6.90	3.00	0.300	6.210		
			1	15.00	2.70	0.420	17.010		
			1	4.00	2.00	0.450	3.600		
			1	5.00	3.00	0.600	9.000		
			1	13.00	2.50	0.200	6.500		
			1	19.00	3.00	0.200	11.400		
			1	15.00	2.80	0.200	8.400		
			1	20.00	0.99	0.250	4.950		
			2	5.00	2.80	0.230	6.440		
			1	6.50	1.20	0.200	1.560		
			1	14.50	1.50	0.300	6.525		
			1	6.00	1.00	0.300	1.800		
			1	21.00	3.00	0.320	20.160	18.90	
			1	2.00	1.50	0.300	0.900		
			1	6.00	1.50	0.200	1.800		
			2	5.00	3.00	0.300	9.000		
			1	15.00	3.00	0.300	13.500		
			1	17.00	2.80	0.250	11.900		
			1	22.00	3.00	0.250	16.500	148.50	
			1	27.00	3.20	0.300	25.920		
			1	8.00	3.40	0.200	5.440		
			8.000 KM to 8.926 KM						
			1	17.00	2.80	0.200	9.520		
			1	27.00	3.20	0.300	25.920		
			1	19.00	5.50	0.900	94.050		
			1	14.00	3.25	0.500	22.750		
			1	8.00	3.40	0.210	5.712		
			Total						

1068.389 1867.76 2054278 1995,494.23 2054278

14.12.2020
JE

15/12/2020
AL

15/12/2020