

FDR

DISTRICT :- DARBHANGA

BLOCK :- BAHADURPUR

Name of Road :- Ganouli Reo sadak se Yadav tola

Length of the Road:- 1.875 KM.

Effective Length 0.112 KM.

GENERAL ABSTRACT OF COST

Sl No.	Item of Work	Amount (in Rs.)
1	Cost for restoration	3,38,868.63 ✓
2	Add 12 % GST	40,664.24 ✓
3	Add Seigniorage	19,286.06 ✓
4	Add 1 % Labour Cess	3,388.69 ✓
Total cost:-		4,02,207.61 ✓ 4,02,208 = 00

14/12/2020
Junior Engineer
Bahadurpur

14/12/20
Assistant Engineer
Bahadurpur

16/12/20
Executive Engineer
R.W.D.(W) Division, Darbhanga-1

कार्यपालक अभियंता, जिला कारागार, कारागारमंडल - 401521 का पत्रांक 542 अ.सं.
दिनांक 07/04/2021 को द्वारा समर्पित जाये प्रतिक्रिया के अतिरिक्त 42।
Post-free to T/A for Rs 402,208 = 00 (Rupees Four Lacs Two -
thousand two hundred eight only.)

09.04.21
Superintending Engineer
RWD, Works Circle, Darbhanga
09/04/2021

Detailed estimate for making moterale road.

Name of Road :- Ganouli Reo sadak se yadav tola Teliyapokhar
BLOCK :- BAHADURPUR
DISTRICT :- DARBHANGA
R.W.D. Works Division Darbhanga-1

Sl. No.	Item	Unit	No	Length (m)	Breadth (m)	Depth / Height (m)	Quantity	Rate	Amount
1	Labour and placing of brick bats with light raming including cost of brick bats by tractor	cum		From Yadav Tola					
				0.100 KM to 0.500 KM.					
			1	4.50	1.85	0.800	6.660		
			1	18.50	1.65	1.000	30.525		
			1	13.50	1.80	1.000	24.300		
			1	9.50	2.10	0.700	13.965		
			1	10.50	1.30	0.800	10.920		
			1	5.50	3.80	0.800	16.720		
			1	2.50	0.80	0.300	0.600		
			1	3.80	1.70	0.400	2.584		
			1	3.50	1.05	0.300	1.103		
			1	3.80	2.20	0.600	5.016		
			1	12.50	2.43	0.800	24.250		
			1	2.50	1.00	0.400	1.000		
			1	13.50	3.80	0.800	41.040		
			1	1.00	1.00	0.300	0.300		
			1	3.50	0.80	0.600	1.680		
			1	3.20	0.80	0.300	0.768		
						Total	181.431	1867.76	338869
									338869

14/12/2020
 Junior Engineer
 Bahadurpur

14/12/20
 Assistant Engineer
 Bahadurpur

14/12/20
 Executive Engineer
 R.W.D.(W) Division, Darbhanga-1