

FDR

**DISTRICT :- DARBHANGA**

**BLOCK :- BAHADURPUR**

**Name of Raad :- Primary School Pokharsam (Booth No. 177) Road  
moterable work.**

**Length of the Road:- 1.500 KM.  
Effective Length 0.043 KM.**

**GENERAL ABSTRACT OF COST**

| Sl No. | Item of Work         | Amount             |
|--------|----------------------|--------------------|
|        |                      | (in Rs.)           |
| 1      | Cost for restoration | 1,67,012.92        |
| 2      | Add 12 % GST         | 20,041.55          |
| 3      | Add 1 % Labour Cess  | 1,670.13           |
| 4      | Seigniorage Fee      | 9,647.79           |
|        | <b>Total cost:-</b>  | <b>1,98,372.39</b> |

Say Rs. 1,98,372-00.

*[Signature]*  
15.12.2020.  
Junior Engineer  
Bahadurpur

*[Signature]*  
Assistant Engineer  
Bahadurpur

*[Signature]*  
Executive Engineer  
R.W.D.(W) Division, Darbhanga-1

समयावधि अर्थात्, रात काराको, कार्य-शेडल - कुमारीय का यन्त्र:- 542 अर्थात्/  
दिनांक:- 07/04/2021 के द्वारा लापिस- ऑफ- यन्त्रों के आधार पर —

Post-fee to T/A for Rs. 1,98,372-00 (Rupees one lakh —  
— ninety eight thousand three hundred seventy two) only.

*[Signature]*  
09.04.21  
Superintending Engineer  
RWD, Works Circle, Darbhanga  
09/04/2021

**Detailed estimate for making moterable road.**

Name of Raad :- Primary School Pokharsam (Booth No. 177) Road moterable work.  
 BLOCK :- BAHADURUR  
 DISTRICT :- DARBHANGA  
 R.W.D. Works Division Darbhanga-1

| Sl. No. | Item                                                                                    | Unit | No.              | Length (m) | Av. Breadth (m) | Av. Depth / Height (m) | Quantity | Rate    | Amount    |
|---------|-----------------------------------------------------------------------------------------|------|------------------|------------|-----------------|------------------------|----------|---------|-----------|
| 1       | Labour and Placing Brick Bats with Light raming including cost of brick bats by tractor | cum  | Near School      |            |                 |                        |          |         |           |
|         |                                                                                         |      | 1                | 14.00      | 3.50            | 0.500                  | 24.500   |         |           |
|         |                                                                                         |      | 1                | 16.00      | 3.00            | 0.450                  | 21.600   |         |           |
|         |                                                                                         |      | Near RCC Culvert |            |                 |                        |          |         |           |
|         |                                                                                         |      | 1                | 6.30       | 4.00            | 0.800                  | 20.160   |         |           |
|         |                                                                                         |      | 1                | 7.00       | 3.50            | 1.000                  | 24.500   |         |           |
|         |                                                                                         |      |                  |            |                 |                        | 90.760   | 1840.16 | 167012.92 |

*15-12-2020*  
 Junior Engineer  
 Bahadurpur

*15/12/20*  
 Assistant Engineer  
 Bahadurpur

*18/12/20*  
 Executive Engineer  
 R.W.D.(W) Division, Darbhanga-1