

FDR

DISTRICT :- DARBHANGA

BLOCK :- BAHERI

Name of Raad :- Khangraittha to Hanuman Nagar

Length of the Road:- 2.063 KM.

Effective Length 0.033 KM.

GENERAL ABSTRACT OF COST

Sl No.	Item of Work	Amount
		(in Rs.)
1	Cost for restoration	90,212.81
2	Add 12 % GST	10,825.54
3	Add 1 % Labour Cess	902.13
4	Seigniorage Fee	5,134.29
	Total cost:-	1,07,074.76

Rahant
5-12-2020
Junior Engineer
Bahadurpur

dh
16/11/20
Assistant Engineer
Bahadurpur

10/12/20
Executive Engineer
R.W.D.(W) Division, Darbhanga-1

कार्यपालक अभियंता द्वारा कार विर कार्य प्रमंडल-कुलपएस के पत्रांक 542 अंकु
दिनांक 07/04/2021 / के द्वारा समर्पित ऑन-प्रतिवेदन के आवाज़ पर।

Post-Facto T/A दर Rs - 1,07,075 = (Rupees One Lacs Seven
thousand seventy five) only.

09-04-21
Superintending Engineer
RWD, Works Circle, Darbhanga
09/04/2021

Head - FDR 1

Name of Work - Khangsalika to Hanuman Nagar

Situation of Work - Block Bahari

Agency by which work is executed - Departmental

Date of Measurement -

No. and date of agreement

(These four lines should be repeated at the commencement of the measurement relating to each work)

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
Date of entry:-	15.04			2021	
① Labour and Placing					
brick bats with light					
ramming including cost of					
brick bats by tractor and					
1X	25.00	3.00	0.50		37.50 m ³
1X	8.00	3.00	0.45		10.80
					48.30 m ³
Signature	15.04.2021				

ABSTRACT OF COST.

① Labour and placing Brick			
Bats with light ramming			
including cost of brick			
Bats by tractor and			
V.P. ① Q = 48.30 m ³			
@ Rs. 1867 = 76/m ³			Rs. 90,213.00
			Rs. 90,213.00
Add. G.S.T. (12%)			Rs. 10,826.00
Add. 1% Labour Cess			Rs. 902.00
Add. Surcharge for			
brick bats. Q = 48.30 m ³			
@ Rs. 1063 = 00/m ³ x 10%			Rs. 5,134.00
			Rs. 1,07,075.00

Signature
15.04.2021

Signature
15/4/21
ne

Signature
15/4
EC