

FDR

DISTRICT :- DARBHANGA

BLOCK :- BAHADURPUR

Name of Raad :- Hathauri Ghat Par Bane RCC Pool tak


Length of the Road:- 1.125KM


Effective Length 0.28KM


GENERAL ABSTRACT OF COST

No.	Item of Work	Amount (in Rs.)
1	Cost for restoration	2,04,773.74
2	Add 12 % GST	24,572.85
3	Add Seigniorage	11,654.31
4	Add 1 % Labour Cess	2,047.74
Total cost:-		2,43,048.63

say Rs. 2,43,049=00.



16.12.2020
Junior Engineer
Baheri


15/12/20
Assistant Engineer
Baheri


Executive Engineer
R.W.D.(W) Division, Darbhanga-1

आप्रमाणित प्रमाणित, जहां जा कि, आप्रमाणित - अनुपलब्ध का पत्रांक: 542 अ/30
दिनांक: 07/04/2021 के द्वारा समिति पांच प्रतिवेदन के आधार पर -

Post facto T/A for Rs. 2,43,049=00 (Rupees Two Lacs
fourty three thousand forty nine) only.


09.04.21
Superintending Engineer
RWD, Works Circle, Darbhanga
09/04/2021

Detailed estimate for making moterable road.

Hathauri Ghat Par bane RCC Pool tak

Baheri

DARBHANGA

R.W.D.(W) Division Darbhanga-1

Item	Unit	No.	Length (m)	Breadth (m)	Depth / Height (m)	Quantity	Rate	Amount	
Labour and placing of brick bats with light raming including cost of brick bats by tractor	cum	From Hathauri Ghat							
		0 KM to 0.500 KM.							
		1	16.00	2.86	0.400	18.304			
		1	1.00	2.00	0.400	0.800			
		1	1.20	1.00	0.700	0.840			
		1	1.00	1.20	0.600	0.720			
		1	1.10	1.00	0.700	0.770			
		1	2.00	1.50	0.800	2.400			
		2	2.80	2.00	1.000	11.200			
		1	2.80	1.00	0.900	2.520			
		1	2.50	1.40	0.600	2.100			
		1	4.00	1.80	0.850	6.120			
		2	4.40	1.00	0.850	7.480			
		1	2.50	2.40	0.900	5.400			
		1	2.00	2.20	0.750	3.300			
		1	1.50	1.20	0.700	1.260			
		1	2.00	1.10	0.600	1.320			
		1	1.00	2.00	0.400	0.800			
		1	2.00	1.35	0.700	1.890			
		0.5 KM to 1.125 KM.							
		1	2.10	1.50	0.900	2.835			
		1	1.00	1.10	0.600	0.660			
		1	2.00	1.50	0.450	1.350			
		1	1.00	1.30	0.600	0.780			
		2	2.00	2.00	0.200	1.600			
		2	2.00	1.00	0.600	2.400			
		1	1.00	1.00	0.150	0.150			
		1	2.00	1.00	0.700	1.400			
		1	8.00	2.00	0.200	3.200			
		1	2.00	1.00	0.600	1.200			
		1	3.00	1.20	0.700	2.520			
		1	2.00	1.20	1.200	2.880			
		3	1.00	1.20	0.750	2.700			
		2	3.00	1.40	1.300	10.920			
		1	2.00	1.00	1.000	2.000			
		1	2.00	1.00	1.200	2.400			
		1	2.40	1.40	0.700	2.352			
		1	1.00	1.10	0.600	0.660			
		1	1.50	1.35	0.200	0.405			
					Total	109.636	1867.76	204773.74	204773.74

10.12.2020
Junior Engineer
Baheri

15/12/20
Assistant Engineer
Baheri

Executive Engineer
R.W.D.(W) Division, Darbhanga-1