

Estimate for motorability of road damaged by flood from Haripur Chowk to Thakurlan Tola for Year 2019

d. MR 3054

Length : 0.9 KM

Item No.	Name of Item	unit	No	Length	Width	Height	Qty.	Rate	Amount
	Providing and filling brick bats in ditches including cost of brick bats and labour all complete job as per specification and direction of E/I.	cum	As Per Appendix 1				132.48 122.392	1867.76	247440.84 2,28,599.00
	Laying Cement Concrete Pipe NP3 600 mm dia (buried conduits) on first class bedding of granular material including fixing collar with cement sand mortar 1:2	M	As Per Appendix 2				22.50	2305.44	51872.31
									299313.15 2,80,471.00
								Add 12% GST	35917.68 33,652.00
								Add 1% Labour Cess	2993.13 2,825.00
								TOTAL (in Re.)	338223.86

Say (in Re.) 338224.00

S. Fee + 13010.00

[Signature]
25/11/20

Junior Engineer,
Rural Works Department,
Works Section, Pandaul

[Signature]
24/11/20

Assistant Engineer,
Rural Works Department,
Works Sub Division, Pandaul

[Signature]
24/11

Executive Engineer,
Rural Works Department,
Works Division, Madhubani

Total = 3,29,943

सहायक अभियंता, ग्राम कटो वि, कार्य प्रगति 4034-4 (मंदा) डी
प्राति: - 05 अक्टूबर दिनांक: - 16.01.2021 के द्वारा सार्वजनिक कार्य प्रगति के
आवक पर।

Post - Fee to T/A for Re 3,29,943.00 (Rupee -
Three lac twenty nine thousand nine hundred forty three)

[Signature]
22.01.21

Superintending Engineer
RWD, Works Circle, Darbhanga
22/01/2021

Name of Road:- Haripur Chowk to Thakurani Tola

Scheme :- MR 3054

Length : 0.900

Block : Pandaul

Appendix - I

Measurement for restoration of Embankment & Shoulder with Brick Bat

Sl. No.	Chainage (in m)	No.	Length (in m)	width (in m)	Thickness (in m)	Quantity (cum)
1	500.000	1.00	5.10	5.75 (av.)	$\frac{1.25 + 1.00}{2} \times 1.00$	55.21 43.84
2	550.000	1.00	5.00	5.00 (av.)	$\frac{1.00 + 0.75}{2} \times 1.00$	52.60 40.30
3	600.000	1.00	5.00	$\frac{5.00 + 4.00}{2}$ (av.)	$\frac{1.00 + 0.75}{2} \times 1.00$	24.88 48.00
					TOTAL	132.49

$T = 132.49 \text{ m}^3$
 $132.49 \text{ m}^3 \times 1.04 = 137.79 \text{ m}^3$

Laying Cement Concrete Pipe 600 mm dia RPS (buried)

Rate Rs. 8

Sl. No.	Chainage (in m)	No.	Length (in m)	width (in m)	Thickness (in m)	Quantity (cum)
1	500.000	3.00	2.50			7.50
2	550.000	3.00	2.50			7.50
3	600.000	3.00	2.50			7.50
					TOTAL	22.50

$1 \times 0.75 \times 0.75 \times 0.75 \times 22.50 = 9.94843$

[Signature]
24/11/20

Junior Engineer
Rural Works Department,
Works Section, Pandaul

[Signature]
24/11/20

Assistant Engineer,
Rural Works Department,
Works Sub Division, Pandaul

[Signature]
24/11

Executive Engineer
Rural Works Department,
Works Division, Madhubani

पलांक 05 कैम्प दरभंगा दिनांक 16/01/21

सेवा में

अधीक्षण अभियंता
ग्रा० का० वि०, कार्य
अंचल, दरभंगा

विषय:- वर्ष 2020 में बाढ़/अतिवृष्टि से क्षतिग्रस्त पथों/
पुलों में कराये गये पुर्नस्थापन कार्य से
संबंधित पथों का प्रत्यक्षन के संबंध में।
प्रसंग:- भवदीय का पलांक 2863 अनु दि० 02/12/2020

महोदय,

उपयुक्त विषयक प्रासंगिक पत्र से प्राप्त
थातायात पुर्नस्थापन कार्य का निम्नांकित
प्रत्यक्षन गठित जोयदल श्री उपेन्द्र कुमार
राम सह अ० कार्य अवर प्रमंडल, दानश्यामपुर एवं
मौ आरिफ हुसैन कार्य प्रशाखा, मनीगाछी द्वारा
जोयपरान्त प्रतिहस्ताक्षर कर आवश्यक
अंगीतरु कार्रवाई हेतु समर्पित किया जा
रहा है।

- ① Tos Nautolia to Siswa - 4.175Km
- ② Haripur Chowk to Thakurani tola - 0.900Km
- ③ Hat Sahaspathi to Phutani Chowk - 1.10Km
- ④ Tos Siswana to Shubhanikarpur - 7.815Km
- ⑤ NH05 Kuso yadav house to jibachhpal Bhangy Bhatta - 1.625km
- ⑥ Bhalani to Haripur Dihatol - 1.40Km
- ⑦ MMGSY Road to Muslim tola Keota - 1.798Km

अनु० - यथोक्त

विश्वासभाजन

दिनांक 16/01/21

सहायक अभियंता
ग्रा० का० वि०, कार्य
अवर प्रमंडल, दरभंगा