

Inspection Report for Flood Damage Work

Date:-.....

1.Name of PIUs:- CC PWD Area

2.Name of Block:- Area

3.Name of Road:- Berhampur to parwalakota by Tola

A. For Road

1.Damage Location/Chainage :- 314

2.Damage Length :- 1210 m

3.Nature of Damage :- breached

4.Details of Restoration Works:-

(i.)Material being used in Restoration Works:- B/Bal

(ii.)Equipments/Tools being used in Restoration works:- PLY, Trench, JCB

(iii.)Procedure taken up in Restoration works:-

(iv.)Restored Length :- 1210 m

B. For Bridge

1. Damage Location/Chainage:-

2.Damage Length :-

3.Nature of Damage :-

4.Details of Restoration Works:-

(i.)Material being used in Restoration Works:-

(ii.)Equipments/Tools being used in Restoration works:-

(iii.)Procedure taken up in Restoration works:-

(iv.)Restored Length :

 21.9.22

Signature of JE/AE/EE


Signature

(Name of Inspector)

प्रतिवेदन

पथ का नाम :- ~~Highway to Bhatnagar Road~~ Bhatnagar Road

कार्य का नाम :- PDR

में बाढ़ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।

संलग्न प्राक्कलन 10.06.2020 को प्रखण्ड में आगी भीषण बाढ़ से क्षतिग्रस्त 24/1/20


में बाढ़ क्षतिग्रस्त मरम्मत मद से यातायात चालू करने हेतु तैयार किया गया है जिसकी प्राक्कलित लागत 157216 है।

उक्त पथ का निर्माण योनान्तर्गत हुआ है एवं योजना अनुसंधान

अवधि में .5]...। पथ के कटे (क्षतिग्रस्त)


भाग में आवश्यकता अनुसार Hume Pipe, Bamboo, लोकल बालू एवं Brick Bats देने के बाद यातायात चालू कराया गया है। पथ के विभिन्न हिस्से में कराये गये कार्य का विवरणी स्पष्ट रूप से प्राक्कलन में दर्शाया गया है।

प्राक्कलन मदों का दर वर्तमान अनुसूचित दर के अनुरूप है।


K. S. Singh

कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा,।

सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमण्डल,।


K. S. Singh

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल,

SUMMARY OF COST ESTIMATE FOR THE PROJECT

NAME OF ROAD :-	Biripull to Palrwa Khorl Ray Tola	
DISTRICT :-	Araria	
BLOCK :-	Araria	
Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Supply and Carriage of brick bats	4404793.28
	SUB TOTAL COST =	4404793.28
	ADD GST @ 12% =	528575.19
	Add Labour cess @ 1% =	44047.93
	Add Contingency @ 1% =	0.00
	TOTAL. (RS.) =	4977416

[Signature]
J.E

[Signature]
A.E

[Signature]
E.E

S.E

T/A for Rs. 4977416 = (Forty Nine Lakh Seventy Seven thousand four hundred sixteen only)

[Signature]
28/11/20

Bill of Quantity

NAME OF ROAD -		Biripuli to Palwa Khorl Ray Tola		
DISTRICT -		Araria		
BLOCK -		Araria		
Sl. No.	DESCRIPTION OF ITEMS	QUANTITY	RATE (Rs.)	AMOUNT (Rs.)
1	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.	2053.50	2,145.02	4404793.28
		A) SUB TOTAL =		4404793.28
		TOTAL COST =		4404793

J.E

A.E

E.E

No.	DESCRIPTION OF ITEMS	UNIT	Nos.	L(m)	B(m)	D(m)	QUANTITY	RATE (Rs.)	AMOUNT (Rs.)
1	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.								
1st km		cum	1	200.00	3.00	0.60	360.00		
		cum	1	100.00	3.00	0.65	195.00		
		cum	1	60.00	3.00	0.30	54.00		
		cum	1	60.00	3.00	0.40	72.00		
		cum	1	50.00	3.00	1.50	225.00		
		cum	1	90.00	3.00	0.50	135.00		
		cum	1	40.00	3.00	1.50	180.00		
		cum	1	100.00	3.00	0.40	120.00		
		cum	1	20.00	3.00	0.50	30.00		
		cum	1	40.00	3.00	0.85	102.00		
2nd km		cum	1	140.00	3.00	0.60	252.00		
		cum	1	70.00	3.00	0.30	63.00		
		cum	1	50.00	3.00	0.30	45.00		
		cum	1	100.00	3.00	0.40	120.00		
		cum	1	10.00	3.00	0.85	25.50		
3rd km		cum	1	60.00	1.50	0.50	45.00		
		cum	1	20.00	3.00	0.50	30.00		
		cum		total qty :-				2,145.02	4404793.28

