

Inspection Report for Flood Damage Work

Date:-.....

1. Name of PIUs:- Ex. Ea. R.W.D (Work Div) - Araria
2. Name of Block:- Jokiha
3. Name of Road:- Rani to Mehadi Nagar

A. For Road

1. Damage Location/Chainage :- CH- 4500-4507
2. Damage Length :- 2x7 M
3. Nature of Damage :- Approach of Bridge.
4. Details of Restoration Works:-
(i.) Material being used in Restoration Works:- Brick bats, local sand and bamboo
(ii.) Equipments/Tools being used in Restoration works:- Tractor with Trolley.
(iii.) Procedure taken up in Restoration works:- filled all cuts properly in damage area.
(iv.) Restored Length :- 2x7 M

B. For Bridge

1. Damage Location/Chainage:-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works:- N.A.
(i.) Material being used in Restoration Works:-
(ii.) Equipments/Tools being used in Restoration works:-
(iii.) Procedure taken up in Restoration works:-
(iv.) Restored Length :-

Signature of JE/AE/EE
23-12-2018

Signature
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमण्डल- किशनगंज-2

ABSTRACT


Name of Road : Rani to Mehdi nagar


Length : 7.700 km


District : Araria

Block : Jokihat


Sl. No	Particulars		Total Cost (in Rs.)
1	Cost of Road Restoration work	:	572472
2	Add G.S.T. @ 12%	:	68697
3	Add Labour Cess @ 1%	:	5725
Total Cost			646893
say			6.47 6,46,900/-


J. E.


23.12.2020
A. E.


E. E.

T/A' for Rs-6,46,900/- (Rupees Six Lac. forty Six thousand Nine hundred) only


12/12/20

ESTIMATE FOR ROAD RESTORATION WORK

Name of Road:

Rant to Mehdi nagar

Block

Jokihat

length

7.70 km

Sl. No.	SSR Item No.	Chainage In M.	Cutting In M.	Description	No.	Length (M)	Width (M)	H/D (M)	Qty.	Unit	Rate (in Rs.)	Amount (in Rs.)
1	8.7.7			Providing and cutting 62 mm to 75 mm dia bamboo pile to size and making shoes and driving etc. all complete job as per specification and direction of E/I								
		4500	4507	7	Approach pipe culvert	2	35	4.50	315.00			
									315.00	M	50.20	15813
2	8.7.8			Providing, fitting & fixing 62mm to 75 mm dia bamboo runners in position at every vertical piles with 150 m long nails or 38 mm G.I. wire including cost of G.I. or nails all complete job as per specification and direction of E/I								
		4500	4507	7		2	8.00	7.00	112.00			
									112.00	M	28.53	3196
3				Providing and Filling empty cement bags with local sand, stitching the bags and placing including supply of stuff etc. all complete job as per specification and direction of E/I								
		4500	4507	7		2	7.00	1.5	2.5	52.50		
									52.50			
					29.4 bag=1m3							
					1543.6 bag				1544	/bags	38.16	58965
4				Filling and spreading local sand over brick bats as per drawing and technical specification Clause 305.3.9								
		4500	4507	7	$(3.75+5.5+3.75)/3=4.33$	3	7	4.5	4.33	409.19		
									409.19			
				Deduction for H.P. 1000MM dia	0	0.785	1.52	7.50	0.00			
									409.19	cum	626.89	256514.00
5				Providing brick bats including spreading laying hand packing and compacting with C.I. Hammer in layers not exceeding 75 mm thick including cost of light, barriers, danger signals, chowkidar, taxes, royalty etc. all complete job as per specification and direction of E/I excluding carriage cost of bricks.								
		4500	4507	7	$(0.90+2.75+0.9)/3=1.51$	3	7	3.5	1.51	110.99		
									110.99	cum	2145.02	238068.00
6				Providing and laying of R.C.C. Hume pipe 150mm dia with all complete job as per specification and direction of E/I								
					0	3	2.5		0.00	M	4781.89	0.00
											Total=	572472
											Add GST 12%	68097
											Labour cess 1%	5725
											Total=	646893
											SAY=	646893

23/12/2020
J.E.
RWD (W) SUB DIV JOKIHAT

23.12.2020
A.E.
RWD (W) SUB DIV

646900
23/12/2020
E.E.
RWD ARARIA