

INSPECTION REPORT FOR FLOOD DAMAGE WORK

Date :-

1 Name of P.U. :- Executive Engineer, RWD, (W) Division, ARARIA

2 Name of Block :- Kungabanta

3 Name of Road :- L043 to Parbatta

4 FOR ROAD

1 Damage Location/ Chainage :- CH - 12006 - 1230 M

2 Damage Length :- $(230 + 9.4) M = 324 M$

3 Nature of damage :- Crust and Flank washed out.

4 Details of Restoration work

i Material being in Restoration work :- Soil, Local Sand, Sand bag, Brickbat Bamboo etc.

ii Equipments/ Tools being used in Restoration works :- Tractor with trolly & others.

iii Procedure taken up in Restoration work :- Filling all damaged portion of Crust and Flank with above Material

iv Restored Length M

5 FOR BRIDGE

1 Damage Location/ Chainage :-

2 Damage Length :-

3 Nature of damage :-

4 Details of Restoration work


i Material being in Restoration work :-


ii Equipments/ Tools being used in Restoration works


iii Procedure taken up in Restoration work


iv Restored Length

Not Applicable


93/12/020
J.E.


22.12.2020
A.E.



23/12/20
E.E.



Name of Inspector
EE, RWD, Kishanganj-2


GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : L043 TO PARBATT
DISTRICT ARARIA
DIVISION ARARIA
BLOCK KURSAKANTA
LENGTH OF ROAD (IN KM) 4.818


Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	BRIKCK BAT	10.371
2	SAND BAGS	0.229
3	BAMBOO WORK	1.257
4	HUME PIPE	0.226
TOTAL COST OF PROJECT =		12.082
Add G.S.T. @ 12%		1.45
Add Labour Cess @ 1%		0.121
Total Cost of Restoration Work =		13.653


22/12/2020
JE
RWD


22.12.2020
AE
RWD


22/12/20
EE
RWD

T/A for Rs 13,65,300/- (Rupees thirteen lakhs sixty five thousand three hundred) only.


12/8/24

LOT 3 (3) AND 3 (4)

Sl. No.	SDB SL. NO.	MORD Ref. No.	Description	Unit	NOS	LENGTH	WIDTH	HEIGHT	QUANTITY	RATE	AMOUNT (in Rs.)
1	4.5		Brick Bats								
			Providing Brick Bats including, Spreading, Laying Compacting with C.I. Hammer all complete job as per Specification and Direction E/I.								
			C/O To ANNEXURE "A"						488.660		
			Less H.P. Qty. $2 \times (3.14) \times (1.15/2)^2 \times 7.50$						-5.190		
				Cum					483.470	2145.020	1037052.82
2	9.3	(c)	Providing and Laying Reinforced Cement Concrete Pipe NP3 as per design.								
			Providing and laying reinforced cement concrete pipe NP3 For Restoration (1000 mm dia Single Row)								
					2	2.50			5.000		
				RM					5.000	4519.780	22598.90
3	10.7.40 WRD		Labour for filling Cement Bag, swing and laying materials								
					600				600.000		
				Bag					600.000	38.150	22890.00
4	14.17		Labour for driving 62 MM to 75 MM dia Bamboo Piles Including cutting to in proper size and shoes etc complete job. (Bamboo Piles c/c 0.3 m)								
			CH - 1200	m	2 x 21	42.00			140		
			Total Length						140		
									1867		
			Length / 0.3 = Pile Length x 4 = Rm						1867	50.20	93723.4
5	14.19		Supplying fitting and fixing of bamboo 62 mm to 75 mm dia runners fixed at every vertical pile with nails 20 S.W.G G.I Wire								
			Bamboo Runner c/c 0.3 m Upto 1.5 mt. @ (2.50/0.300)	mts.	8.00	140.00			1120		
									1120.000	28.53	31953.6
										Total Cost fo Flood Protective work (In Rs.) =	1208218.72
										Total Cost fo Flood Protective work (In Lakh) =	12.082

JE.,
22/12/2020

A.E.,
22/12/2020

E.E.