

Inspection Report for Flood Damage Work

Date:- 21.09.20

- 1.Name of PIUs:- EE RWD Arara
2.Name of Block:- Arara
3.Name of Road:- Kanan' to Belang'

A. For Road

- 1.Damage Location/Chainage :- 1st Cr
2.Damage Length :- 15 m
3.Nature of Damage :- breach
4.Details of Restoration Works:-
(i.)Material being used in Restoration Works:- B/Bs, barbed wire, etc. 14.8
(ii.)Equipments/Tools being used in Restoration works:- Tractor, etc.
(iii.)Procedure taken up in Restoration works:-
(iv.)Restored Length :- 15 m

B. For Bridge

1. Damage Location/Chainage:-
2.Damage Length :-
3.Nature of Damage :-
4.Details of Restoration Works:-
(i.)Material being used in Restoration Works:-
(ii.)Equipments/Tools being used in Restoration works:-
(iii.)Procedure taken up in Restoration works:-
(iv.)Restored Length :

N/A

Signature of JE/AE/EE
21/9/20

Signature

(Name of Inspector)

प्रतिवेदन


पथ का नाम :-


कार्य का नाम :-

में बाढ़ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।

संलग्न प्राक्कलन 10.06.2020 को प्रखण्ड में आयी भीषण बाढ़ से क्षतिग्रस्त
..... में बाढ़ क्षतिग्रस्त मरम्मति मद से यातायात चालू करने हेतु तैय्यर किया गया है
जिसकी प्राक्कलित लागत है।
उक्त पथ का निर्माण योनान्तर्गत हुआ है एवं योजना अनुरक्षण
अवधि में। पथ के कटे (क्षतिग्रस्त)
भाग में आवश्यकता अनुसार Hume Pipe, Bamboo, लोकल बालू एवं Brick Bats देने के बाद
यातायात चालू कराया गया है। पथ के विभिन्न हिस्से में कराये गये कार्य का विवरणी स्पष्ट
रूप से प्राक्कलन में दर्शाया गया है।
प्राक्कलन मदों का दर वर्तमान अनुसूचित दर के अनुरूप है।


कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा,।


सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमण्डल,।


कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल,।

SUMMARY OF COST ESTIMATE FOR THE PROJECT		
NAME OF ROAD :-	Kanin to Bhangi	
DISTRICT :-	Araria	
BLOCK :-	Araria	
Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Labour for cutting 62mm to 75mm dia bamboo	3614.40
2	Supplying of EC bag, of local sand	36349.94
3	Supply and Carriage of brick bats	354196.00
4	Supply, laying and carriage of 1000 mm HPC	71728.40
	SUB TOTAL COST =	465888.74
	ADD GST @12% =	55906.65
	Add Labour cess @ 1% =	4658.89
	Add Contingency @ 1% =	0.00
	TOTAL (RS.) =	526454

[Signature]
21.7.20
J.E

[Signature]
21/7/20
A.E


[Signature]
21.7.20
E.E


S.E

T/A for Rs- 5,26,454.00 (Rupees Five Lacs Twenty Six thousand Four Hundred Fifty Four Only.)

[Signature]
21/7/20

Bill of Quantity				
NAME OF ROAD :-		Kanin to Bhangi		
DISTRICT :-		Araria		
BLOCK :-		Araria		
Sl. No.	DESCRIPTION OF ITEMS	QUANTITY	RATE (Rs.)	AMOUNT (Rs.)
1	Labour for cutting 62 mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer- in -charge.	72.00	50.20	3614.40
2	Supplying of EC bag, filling of local sand stitching and placing in position as the direction of Engineer-in-charge.	952.94	38.15	36349.94
3	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.	165.13	2,145.02	354196.00
4	Supplaying and carriage of hume pipe 1000 mm dia , all complete job.	15.00	4,781.89	71728.40
		A) SUB TOTAL =		465888.74
		TOTAL COST =		465889



J.E


A.E


E.E

ESTIMATE FOR REPAIRING / RESTORATION/ MAKING MOTORABLE ROADS DAMAGED DURING FLOOD

NAME OF ROAD :-		Kanin to Bhangi							
DISTRICT :-		Araria							
BLOCK :-		Araria							
Sl. No.	DESCRIPTION OF ITEMS	Unit	Nos.	L(m)	B(m)	D(m)	QUANTITY	RATE (Rs.)	AMOUNT (Rs.)
1	Labour for cutting 62 mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer- in -charge.								
			2	8.00	4.50		72.00		
		Mtr.	total qty:-				72.00	50.20	3,614.40
2	Supplying of EC bag, filling of local sand stitching and placing in position as the direction of Engineer-in-charge.								
		cum	2	8	0.90	2.25	32.40		
	Total No of E C Bags (3.4cum=100Bags)=			32.40	/	0.034	952.94		
		Each	Say No of Bage :-				953	38.15	36349.941

No.	DESCRIPTION OF ITEMS	Unit	Nos.	L(m)	B(m)	D(m)	QUANTITY	RATE (Rs.)	AMOUNT (Rs.)
3	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.								
		cum	1	7.00	3.50	2.25	55.13		
		cum	1	8.00	5.50	2.50	110.00		
		cum	total qty :-				165.13	2,145.02	354196.00
4	Supplaying and carriage of hume pipe 1000 mm dia , all complete job.								
		RM	2	3	2.5		15.00		
		RM	total qty :-				15.00	4,781.89	71728.40
							A) SUB TOTAL =		465888.74
							TOTAL COST =		465888.74
	 Junior Engineer  Asstt. Engineer  Executive Engineer								

S.E
Kishanganj