

Inspection Report for Flood Damage Work

Date:-

1. Name of PIUs:- Ex. ER. R.W.D. Work Div. Araria

2. Name of Block:- Jakiha

3. Name of Road:- MGSY Fatti Bagdhara gogra to Pansairwa.

A. For Road

1. Damage Location/Chainage :- CH- 600 - 835; 950 - 970

2. Damage Length :- $(235 + 20) = 255.00M$ (Side cutting of Road)

3. Nature of Damage :- Crust damaged

4. Details of Restoration Works:-

(i.) Material being used in Restoration Works:- Local Sand, Brick bat & Bamboo

(ii.) Equipments/Tools being used in Restoration works:- Tractor trolley with Tractor

(iii.) Procedure taken up in Restoration works:- filled all cuts properly in damaged area.

(iv.) Restored Length :- 255.00M

B. For Bridge

1. Damage Location/Chainage:-

2. Damage Length :-

3. Nature of Damage :-

4. Details of Restoration Works:-

(i.) Material being used in Restoration Works:-

(ii.) Equipments/Tools being used in Restoration works:-

(iii.) Procedure taken up in Restoration works:-

(iv.) Restored Length :

N.A.

Signature of JE/AE/EE

Signature

कार्यपालक अभियंता
(Name of Inspector)
ग्रामीण कार्य विभाग
कार्य प्रमण्डल- किशनगंज-2.

ABSTRACT


Name of Road : PMGSY Fatki bagdhara gogra to pansairwa

Length : 1.660 km

District : Araria

Block : Jokihat


Sl. No	Particulars		Total Cost (in Rs.)
1	Cost of Road Restoration work	:	1884727
2	Add G.S.T. @ 12%	:	226167
3	Add Labour Cess @ 1%	:	18847
Total Cost			2129742
Say,			21,29,800/- 21.30


J. E.


A. E.


E. E.

T/A for Rs. 21,29,800/- (Rupees Twenty One Lac Twenty Nine Thousand Eight Hundred) only


12/12/21

ESTIMATE FOR ROAD RESTORATION WORK

Name of Road:

PMOSY Fakri bagdharu gagra to pensarwa

Block

Jokihat

length

1.00 km

Sl. No.	SSR Item No.	Chainage in M.	Cutting in M.	Description	No.	Length (M)	Width (M)	H/D (M)	Qty.	Unit	Rate (in Rs.)	Amount (in Rs.)
1	5.7.7			Providing and cutting 62 mm to 75 mm dia bamboo pile to size and making shoes and driving etc. all complete job as per specification and direction of E.I								
		600	635	235 one side	1	783	3		2350.00			
		950	970	20	1	67	3		200.00			
									2550	M	55.20	138610
2	5.7.8			Providing, fitting & fixing 62mm to 75 mm dia bamboo runners in position at every vertical piles with 150 m long nails or 30 avg G.I. wire including cost of G.I. or nails all complete job as per specification and direction of E.I								
		600	635	235	1	4	335		840.00			
		950	970	20	1	4	20		80.00			
									920.00	M	38.03	35191
3				Providing and Filling empty cement bags with local sand, stitching the bags and placing including supply of stuff etc. all complete job as per specification and direction of E.I								
		600	635	235	1	235	0.8	1.5	283.00			
		950	970	20	1	20	0.8	1.5	24.00			
					29	bag=1m3			205.00			
					8995.4	bag			8090	/ bags	38.15	343213
4				Filling and spreading local sand over brick bats as per drawing and technical specification Clause 305.3.9								
		600	635	235	1	235	2.68	2.56	1512			
		950	970	20	1	20	2.15	3.09	133			
									total		1745	
				Deduction for H.P. 1000MM dia	0	0.785	1.52	5.00	0			
				1.52 1.23x1.23=1.52					1745	sum	825.89	1094022.96
5				Providing brick bats including spreading laying hand packing and compacting with C.I. Hammer in layers not exceeding 75 mm thick including cost of light, barriers, danger signals, chowkidar, taxes, royalty etc. all complete job as per specification and direction of E.I excluding carriage cost of bricks								
		600	635	235	1	235	1.75	0.3	123.38			
		950	970	20	1	20	2	0.3	12.00			
									total	135.38	cum	2145.02
6				Providing and laying of R.C.C. Hume pipe 1hp3 in 1000mm dia with all complete job as per specification and direction of E.I								
					0	2	2.5		0.00	M	4781.89	0.00
											Total=	1884727
											Add GST 12%	228187
											Labour cess 1%	18847
											Total=	2129742
											SAY=	2129742

23/12/2020
J.E.
RWD (W) SUB DIV JOKIHAT

23.12.2020
A.E.
RWD (W) SUB DIV

23/12/2020
E.E.
RWD KARAI