

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

CIRCLE – R.W.D. works Circle, Chapra

DIVISION – R.W.D. works Division, Marhaura

Name of Work - Motrable of Road from Amnaur Hussepur Amnaur Road to Khaspatti

Block - Amnaur

Estimated cost - Rs 640367.00

Year : 2020-21

Inspection Report for Flood damage work

Date:

1. Name of PIUs- E.E.R.W.D (W) Madhura.

2. Name of Block/Road- Amarour - Motorable Road from Amarour
Hessapur Amarour Road to Khaspatti

A. For Road

1. Damage Location/Chainage : - 230, 296,

2. Damage Length : 76 M.

3. Nature of Damage : Road cutting due to flood.

4. Details of Restoration :

i Material being used in Restoration

: Brick Bat, Local Sand, Fly-

ii Equipment/Tools being used in Restoration works:

Roller, Grader, Tractor, J.C.B.

iii Procedure taken up in Restoration works

: Brick Bat, Local sand fly
dumping, laying, Roly.

iv Restored Length

: 76.

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

Signature of JE/AE/EE

Signature

AKHILESH KUMAR
(Name of Inspector)

E.E.R.W.D

(W) - DIVISION - SONEPUR

प्रतिवेदन

कार्य का नाम :- *Motable of Road from Amnour Hussapur Amnour Road to Khaspati*
शीर्ष :- FDR
प्राक्कलित राशि:- 640367/-
प्रखण्ड का नाम:- अमनौर

जिला-सारण।

प्रस्तुत प्राक्कलन शीर्ष PMGSY/MMGSY/GTSNY/NABARD/MR-3054 अर्तगत निर्मित/निर्माणाधीन पथ के गत महीने में इस जिला में आये बाढ़/अतिवृष्टि के कारण क्षतिग्रस्त हुए पथों को चलने लायक (Motable) बनाने हेतु विभागीय दिशा-निर्देशानुसार कार्यपालक अभियंता, ग्रा0का0वि0, कार्य प्रमंडल मढ़ौरा के दिशा-निर्देशन में कुल रु0 640367/- के लिए तैयार किया गया है।

आवश्यकतानुसार तत्काल प्रभाव से पथों को चलने लायक बनाने हेतु प्राक्कलन में Bricks Bats, Sand Bag, Hume-Pipe इत्यादी का प्रावधान आवश्यक लम्बाई, चौड़ाई एवं मोटाई में प्राक्कलन के अनुसार प्रावधान किया गया है।

योजना एवं कार्य की महत्ता के साथ-साथ जनहित के लिए अतिउपयोगी प्राक्कलन को कार्यहित में स्वीकृति हेतु प्रस्तुत किया जा रहा है।

25/11/2020
V.B. Amnour

25/11/20
कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, मढ़ौरा।

ABSTRACT OF COST

Name of Work - Motrable of Road from Amnaur Hussepur Amnaur Road to Khaspatti

Block - Amnaur

S.L No.	Particulars	Amount (In Rs.)
A	Cost of Restoration work	
B	Add 12 % GST on (A)	Rs 566696.00
C	Add 1 % L. Cess on (A)	Rs 68004.00
		Rs 5667.00
	Total Cost	Rs 640367.00

J.E
RWD
Amnaur

A.E
R.W.D
Amnaur

E.E
R.W.D
Marhaura

T/A for Rs 640367.00 (See 19th forty thousand
Three hundred sixty seven hundred)

अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, छपरा

me of work :-


Detailed Estimate

Motable of Road from Amnaur Hussepur Amnaur Road to Khaspatti

SI No	Item	No	Length	Width	Avg.H/D	Qty	Unit	Rate	Amount
1	Providing laying and spreading brick bats in Road ditches all complete as per approved design, specifications and direction of E/I	1	15.00	3.80	0.61	34.77			
		1	61.00	3.90	1.07	254.55			
		Total					289.32	cum	1909.87
2	Filling and spreading local sand over brick bats as per drawing and technical specification Clause 305.3.9	1	15.00	3.80	0.10	5.70			
		1	61.00	3.90	0.10	23.79			
		Total					29.49	cum	479.27
TOTAL									566696.00



J.E
R.W.D
Amnaur



A.E
R.W.D
Amnaur



E.E
R.W.D
Marhaura