

estimate for motorability of road damaged by flood from Bhawanipur to Shankarpur for Year 2019

d - MR 3054

Length : 3.1 KM

Item No.	Name of Item	unit	No	Length	Width	Height	Qty.	Rate	Amount
	Providing and filling brick bats in ditches including cost of brick bats and labour all complete job as per specification and direction of E.I.	cum	As Per Appendix 1				510-11 472.22 113	1840.16	938684.02 8,68,960.00
	Laying Cement Concrete Pipe NP3 1000 mm dia (buried conduits) on first class bedding of granular material including fixing collar with cement sand mortar 1:2	M	As Per Appendix 2				7.50	3565.04	26737.77 -
									085421.79 8,75,698.00
								Add 12% GST	115850.61 10,74,84.00
								Add 1% Labour Cess	9654.22 8,95,2.00
								TOTAL (In Re.)	1090926.62

Say (In Re.) 1090927.00

Add S.F. Rs. 50,197.00

Total Rs. 10,62,336.00

Junior Engineer,
Rural Works Department,
Works Section, Pandaul

Assistant Engineer,
Rural Works Department,
Works Sub Division, Pandaul

Executive Engineer,
Rural Works Department,
Works Division, Madhubani

सहायक अभियंता, ग्राम कार्य विभाग, कामेश्वर मंडल - दमरगा (सुपु) जिला - 06 कम्प (दमरगा) दिनांक:- 16.01.2021 के द्वारा समर्थित जाँच परीक्षण के आधार पर।

Post-facto T/A Rs. 10,62,336.00 (Rupees - Ten Lacs Sixty two Thousand three hundred thirty six) only.

Superintending Engineer

RWD, Works Circle, Darbhanga

22/01/2021

Name of Road:- Bhawanipur to Shankarpur

Scheme :- MR 3054

Length : 3.100

Block : Pandaul

Appendix - I

Measurement for restoration of Embankment & Shoulder with Brick Bat

L. No.	Chainage (in m)	No.	Length (in m)	width (in m)	Thickness (in m)	Quantity (cum)
1	300.000	1.00	33.00	3.75	$\frac{0.45 + 0.60 + 0.25}{3}$ 0.43 (av.)	74.25 52.594-4 ³
2	320.000	1.00	5.00	1.50	0.60 (av.)	4.50
3	1710.000	1.00	5.00	3.75 1.00-	$\frac{0.75 + 1.25 + 0.25}{3}$ 0.75 (av.)	25.00 16.962-4 ³
4	1715.000	1.00	7.50	2.20	1.85 (av.)	30.53
5	2120.00 to 2500.00	3.00	30.00	3.75	0.60 (av.)	202.50
6		1.00	30.00	3.75	0.45 (av.)	50.63
		1.00	30.00	3.75	0.60 (av.)	67.50
7		1.00	20.00	3.75	0.30 (av.)	22.50
8		1.00	15.00	3.00	0.30 (av.)	13.50
9		1.00	8.00	3.00	0.30 (av.)	7.20
10		1.00	4.00	2.50	0.30 (av.)	3.00
11		1.00	3.00	2.00	0.30 (av.)	1.80
12		1.00	4.00	3.75	0.30 (av.)	4.50
13		1.00	3.00	3.00	0.30 (av.)	2.70
					TOTAL	510.11- 480.0161 ³

Appendix - II

Laying Cement Concrete Pipe NP3 (buried) 1000 mm dia

Sl. No.	Chainage (in m)	No.	Length (in m)	width (in m)	Thickness (in m)	Quantity (cum)
1	1720.000	3.00	2.50	0.00	0.00 (av.)	7.50
					TOTAL	7.50

7440 = 472.22 4³

22/11/20

24/11/2020

22/11/20

Junior Engineer
Rural Works Department,
Works Section, Pandaul

Assistant Engineer,
Rural Works Department,
Works Sub Division, Pandaul

Executive Engineer
Rural Works Department,
Works Division, Madhubai

पतांक ०६ नैम्य (दरभंगा) दिनांक 16/01/21

सेवा में

अधीक्षण आगियता
ग्रा० का० सि०, कार्य
अंचल दरभंगा

विषय:- वर्ष 2020 में बाढ़ / अतिवृष्टि से क्षतिग्रस्त पथों/पुलों में कराये गये पुनरुत्थापन कार्य से संबंधित पथों का प्राक्कलन के संबंध में।

प्रसंग-भवदीय का पतांक 2863 अंक दि० 02/12/2020

महाराज,

उपरिक्त विषयक प्रासंगिक पत्र से प्राप्त आतायात पुनरुत्थापन कार्य का निम्नलिखित प्राक्कलन गठित जॉचदल श्री दिनेश कुमार गुप्ता, स० अ०, ग्रा० का० सि०, कार्य अवर प्रमंडल, कलेश्वर-स्थान खुबू श्री हरेराम, क० अ०, कार्य प्रशासक, जाली द्वारा जॉचोपरान्त प्रति हस्ताक्षर कर आवश्यक अग्रेतर कार्रवाई हेतु मूल में समर्पित किया जा रहा है।

- ① Pakki Road Jamsam to Mahadalit tol - 0.592 Km
- ② Bhawanipur to Shankarpur - 3.10 Km
- ③ To 4 to Navtoli (Bhawanipur) - 4.613 Km
- ④ Hati to Rampatti - 5.40 Km
- ⑤ To 3 to Sarisav Sarji Tol - 1.224 Km
- ⑥ Sarisopahi Sarji tol to NH 57 - 1.550 Km
- ⑦ To 4 Sarisav to Shishup - 7.667 Km
- ⑧ Ramlabari to Udaipur Bithuar - 3.56 Km
- ⑨ Bardiwan to Kakna Railway line - 1.05 Km
- ⑩ Mohanpur middle school to Seema tol - 1.916 Km

अंक - यथोक्त

विरवारगलन

सहायक, आगियता
ग्रा० का० सि०, कार्य
अवर प्रमंडल, दरभंगा