

to for motorability of road damaged by flood from Tarapatti Mettled road to Pallmohan Mettled road for Year 2020

MR 3054


Length : 4.8 KM

Name of Item	unit	No	Length	Width	Height	Qty.	Rate	Amount
Providing and filling brick bats in ditches including cost of brick bats and labour all complete job as per specification and direction of E/I.	cum	As Per Appendix 1				030.07 560.80 1/2	1807.76	1550371.54 10,47,440.00
								1550371.54 10,47,440.00
Add 12% GST								186044.59 12,56,940.00
Add 1% Labour Cost								15503.72 10,49,500.00
Add Seignorage Fee								88238.44 10,49,500.00
TOTAL (In Re.)								1840156.29

Say (in Re.) 1840156.00 12,43,232.00



8.1.21
Junior Engineer,
Rural Works Department,
Works Section, Khajauli


28/01/2021
Assistant Engineer,
Rural Works Department,
Works Sub Division, Khajauli


22/1/21
Executive Engineer,
Rural Works Department,
Works Division, Madhubani

सहायक अभियंता, ग्रामो ग्राम विभाग, नारायणगढ़-3 (मधुबनी) को पत्र:-
मोबा 924, 70 - दिनांक:- 21.02.2021 के अंतर्गत प्राप्त धन-विवरण के
आशय पर।

Post-facto T/A Rs 12,43,232.00 (Rupees Twelve
— lac forty three thousand two hundred thirty two only.)


23.02.21
Superintending Engineer
of RWD, Works Circle, Darbhanga
28/02/2021

Name of Road:- Farapatti Metalled road to Pallmohan Metalled road

Scheme :- MR 1054

Length : 4.800

Block : Khajauli

Appendix - I

Measurement for restoration of Embankment & Shoulder with Brick Bat

Sl. No.	Chainage (in m)	No.	Length (in m)	width (in m)	Thickness (in m)	Quantity (cum)
1	0-700	1.00	10.00	3.00	$\frac{0.75 + 0.90 + 0.90}{3}$ (av.)	27.00 15.50
2		1.00	4.00	2.00	0.75 (av.)	6.00
3	800-900	1.00	9.00	2.50	0.55 (av.)	12.38
4		1.00	3.00	3.00	0.50 (av.)	4.50
5		1.00	4.00	3.00	0.50 (av.)	6.00
6		1.00	4.00	2.00	0.55 (av.)	4.40
7		1.00	2.00	3.00	0.55 (av.)	3.30
8		1.00	2.50	2.00	0.50 (av.)	2.50
9		1.00	2.50	2.00	0.55 (av.)	2.75
10	1000-1100	1.00	4.00	2.50	0.55 (av.)	5.50
11		5.00	3.50	2.00	$\frac{0.15 + 0.72 + 0.72}{3}$ (av.)	25.20 2.60
12		1.00	20.00	3.00	$\frac{0.25 + 0.55 + 0.55}{3}$ (av.)	33.00 20.50
13		1.00	15.00	3.00	$\frac{0.25 + 0.55 + 0.55}{3}$ (av.)	22.50 15.75
14	1100-1200	1.00	14.00	3.00	$\frac{0.25 + 0.55 + 0.55}{3}$ (av.)	23.10 14.50
15		1.00	8.00	3.50	0.40 (av.)	11.20
16		1.00	12.00	3.00	0.30 (av.)	10.80

L No.	Chainage (in m)	No.	Length (in m)	width (in m)	Thickness (in m)	Quantity (cum)
17	1200-1300	1.00	25.00	1.50	0.30 (av.)	11.25
18		1.00	5.00	2.50	0.30 (av.)	3.75
19	1300-1400	1.00	6.00	3.00	0.30 (av.)	5.40
20		1.00	2.00	2.50	0.30 (av.)	1.50
21		1.00	3.00	3.50	0.30 (av.)	3.15
22	1400-1500	1.00	7.50	3.00	$\frac{0.30 + 0.55 + 0.35}{3}$ 0.55 (av.)	42.38 7.875
23		1.00	5.00	4.00	0.55 (av.)	11.00
24		1.00	9.00	3.00	$\frac{0.75 + 0.72 + 0.35}{3}$ 0.72 (av.)	19.44 11.88
25	1500-1600	1.00	4.00	3.00	0.55 (av.)	6.60
26		1.00	5.00	1.50	0.50 (av.)	3.75
27		1.00	42.50	2.00	$\frac{0.15 + 0.25 + 0.25}{3}$ 0.55 (av.)	46.75 26.92
28		1.00	6.00	2.50	0.55 (av.)	8.25
29		1.00	3.00	3.00	0.55 (av.)	4.95
30	1600-1700	1.00	2.00	2.50	0.55 (av.)	2.75
31		1.00	4.00	3.00	0.55 (av.)	6.60
32		1.00	2.00	2.50	0.55 (av.)	2.75
33	1700-1800	1.00	6.00	2.50	0.95 (av.)	14.25
34		1.00	15.00	1.50	0.55 (av.)	12.38
35	1800-1900	1.00	4.00	2.50	0.95 (av.)	9.50
36		1.00	2.00	2.00	0.72 (av.)	2.88
37		1.00	1.00	1.50	0.55 (av.)	0.83

I. No.	Chainage (in m)	No.	Length (in m)	width (in m)	Thickness (in m)	Quantity (cum)
38	1900-2000	1.00	3.00	1.50	0.55 (av.)	2.48
39		1.00	3.00	2.50	0.95 (av.)	7.13
40		1.00	20.00	1.00	0.40 (av.)	8.00
41		1.00	18.00	3.00	$\frac{0.35 + 1.15 + 0.45}{3}$ 0.50 (av.)	50.40 33.50
42	2000-2200	1.00	1.00	1.00	0.40 (av.)	0.40
43		1.00	2.00	2.50	0.55 (av.)	2.75
44		1.00	12.00	1.50	0.55 (av.)	9.90
45		1.00	3.00	2.50	0.40 (av.)	3.00
46		1.00	4.00	3.00	0.50 (av.)	6.00
47		1.00	2.00	2.00	0.35 (av.)	1.40
48	2200-2700	1.00	4.00	3.00	0.75 (av.)	9.00
49		1.00	8.00	3.00	0.55 (av.)	13.20
50		1.00	2.00	1.50	0.35 (av.)	1.05
51		1.00	3.00	2.00	0.50 (av.)	3.00
52		1.00	7.00	1.50	0.45 (av.)	4.73
53		1.00	3.00	2.50	$\frac{0.55 + 1.15 + 0.35}{3}$ 0.50 (av.)	8.25 4.33
54	2700-2800	1.00	4.00	2.50	$\frac{0.55 + 1.15 + 0.35}{3}$ 0.50 (av.)	11.00 5.50
55		1.00	5.00	1.50	0.55 (av.)	4.13
56		1.00	4.00	2.50	$\frac{0.35 + 1.15 + 0.35}{3}$ 0.50 (av.)	11.00 5.50
57		1.00	3.00	1.50	0.50 (av.)	2.25
58	2800-2900	1.00	2.00	2.00	0.40 (av.)	1.60
59		1.00	5.00	1.50	0.40 (av.)	3.00
60		1.00	2.00	2.00	0.25 (av.)	1.00
61		1.00	2.00	2.50	0.30 (av.)	1.50
62		1.00	3.00	2.00	0.30 (av.)	1.80
63		1.00	5.00	1.50	0.55 (av.)	4.13

I. No.	Chainage (in m)	No.	Length (in m)	width (in m)	Thickness (in m)	Quantity (cum)
64	2900-3100	1.00	2.50	1.00	0.50 (av.)	1.25
65		1.00	2.50	2.50	0.30 (av.)	1.88
66		1.00	14.00	2.50	$\frac{0.35 + 0.55 + 0.55}{3}$ 0.55 (av.)	49.25 13.12
67		1.00	2.50	1.50	0.35 (av.)	1.31
68		1.00	12.00	1.50	0.55 (av.)	9.90
69	3100-3200	1.00	3.00	2.00	0.72 (av.)	4.32
70		1.00	12.00	3.00	$\frac{0.50 + 0.55 + 0.55}{3}$ 0.55 (av.)	49.80 13.11
71	3200-3300	1.00	5.00	2.50	0.40 (av.)	7.70
72		1.00	11.00	2.00	0.55 (av.)	6.05
73		1.00	2.00	2.50	0.30 (av.)	0.75
74	3400-3500	1.00	9.00	3.00	0.55 (av.)	7.43
75		1.00	11.00	3.00	0.75 (av.)	12.38
76	3500-3600	1.00	5.00	1.50	0.50 (av.)	1.88
77		1.00	4.00	2.00	0.50 (av.)	2.00
78		1.00	2.00	2.00	0.30 (av.)	0.60
79	3600-3700	1.00	1.50	1.00	0.30 (av.)	0.23
80		1.00	20.00	$\frac{4.00 + 7.00}{2}$ 5.50	$\frac{0.45 + 1.35 + 0.55}{3}$ 1.35 (av.)	162.00 62.46
					TOTAL	830.07

8.1.91.
Junior Engineer
Rural Works Department,
Works Section, Khajauli

13/01/2021
Assistant Engineer
Rural Works Department,
Works Sub Division, Khajauli

560.805 M³
Executive Engineer
Rural Works Department,
Works Division, Madhubai