

Estimate for motorability of road damaged by flood from L022 TO THAN TOL for Year 2020

1- MR 3054

Length : 3.171 KM

Item No.	Name of Item	unit	No	Length	Width	Height	Qty.	Rate	Amount
	Providing and filling brick bats in ditches including cost of brick bats and labour all complete job as per specification and direction of E/I.	cum	As Per Appendix 1				224.70 193.12 NP	1867.76	419685.67 3,60,702.00
									419685.67 3,60,702.00
								Add 12% GST	60362.28 4,21,064.28
								Add 1% Labour Cess	4196.86 3,65,261.14
								Add Seignorage Fee	23886.61 3,89,147.75
								TOTAL (in Re.)	498130.42
								Say (in Re.)	498130.00

[Signature]
8.1.21

Junior Engineer,
Rural Works Department,
Works Section, Khajauli

[Signature]
22/01/21
Assistant Engineer,
Rural Works Department,
Works Sub Division, Khajauli

[Signature]
24.1.21
Executive Engineer,
Rural Works Department,
Works Division, Madhubani

सहायक अभियंता, राप्प कारागार, कार्य अन्तर्गत प्रकल्प, दमरुवा (खग) का पथक -
दमरुवा, 3/1/2021 - दिनांक - 21.02.2021 के द्वारा प्रमाणित किया जाता है कि -

आगत पर -

Post-Feet to T/A Rs. 4,28,122.00 (Rupees -
Four lac twenty eight thousand one hundred twenty-two only.)

[Signature]
23.02.21
Superintending Engineer
RWD, Works Circle, Darbhanga
23/02/2021

Name of Road:-- L022 TO THAN TOL

Scheme :- PMGSY

Length : 3.171

Block : Khajauli

Appendix - 1

Measurement for restoration of Embankment & Shoulder with Brick Bat

Sl. No.	Chainage (in m)	No.	Length (in m)	width (in m)	Thickness (in m)	Quantity (cum)
1	2500 to 3171 3000 to 3100	1.00	6.50	$(3.5+2.5+1.5)/3$	$\frac{0.50+0.75+0.35}{3}$ $(0.5+0.75)/2$	40.16 8.16
2		1.00	6.40	$(3.4+3+2.5)/3$	$(1.3+0.45+0.3)/3$	12.97
3		1.00	1.20	4.15	$\frac{0.85+2.50+1.10}{3}$ 2.50 (av.)	12.45 7.55
4		1.00	6.80	$(4.3+7.6)/2$	$\frac{1.45+1.20+1.25}{3}$ $(3.6+4.4)/2$	60.69 56.54
5		1.00	2.20	1.00	1.10 (av.)	2.42
6		1.00	3.00	$(2.0+1.3)/2$	$(0.9+0.6)/2$	3.71
7	Do-Do	1.00	(2.1+1.6)/2	(4.25+2.2)/2	(2.3+2.1)/2	13.13
8		1.00	12.00	$(3.0+2)/2$	$\frac{0.50+1.60+1.20}{3}$ $(4.6+1.4)/2$	45.00 37.00
9		1.00	21.00	2.75	$(0.5+0.9+0.6)/3$	38.50
10		1.00	14.00	2.75	$(0.5+0.9+0.6)/3$	25.67
					TOTAL	224.70


193.12 H


8.1.21

Junior Engineer
Rural Works Department,
Works Section, Khajauli


22/01/21

Assistant Engineer,
Rural Works Department,
Works Sub Division, Khajauli


24.1.21

Executive Engineer
Rural Works Department,
Works Division, Madhubai