



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR REPAIRING OF ROAD

F.D.R. PART - A (2020)

L081 - T04 TO DHOBIBHITA (TRACK 81)

DETAILED ESTIMATE OF F.D.R. REPAIRING ROAD

ROAD LENGTH	0 TO 4974		
DISTRICT	KISHANGANJ		
BLOCK	THAKURGANJ		
DIVISION	KISHANGANJ - 2		
TOTAL LENGTH OF ROAD		4.974	KM
TOTAL COST OF F.D.R. PART - A		Rs. 19.639	Lacs
ADD G.S.T @ 12%		Rs. 2.357	Lacs
Add Seigniorage Fee @ 10 %		Rs. 1.291	Lacs
TOTAL COST OF RESTORATION WORK In Rs.		Rs. 23.287	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Kishanganj - 2

Inspection Report for flood damage work

Date: 11.12.2020

1. Name of PIUs- E.E. RWD (WORKS) Division Kishanganj-2

2. Name of Block/Road- L081-T04 to Dhobibhatta

A. For Road

1. Damage Location/Chainage : 2910m & 3010

2. Damage Length : 65.6m

3. Nature of Damage : Ditch & flank cutting

4. Details of Restoration :

i Material being used in Restoration

: Brick Bats and Hume pipe

ii Equipment/Tools being used in Restoration works: Tractor

iii Procedure taken up in Restoration works :

iv Restored Length

: 65.6m

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

Signature of JE/AE/EE

11/12/2020
AE

12/12/20

Signature

(Name of Inspector)

TECHNICAL REPORT

Name of Work - FDR To Road From Lo 81- Top to Dhobibhita (Track 81) -
Head - FDR
Estimated cost - 23.287 Lacs

The work done estimate has been framed for the restoration (motarable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

(A) Source of materials

Brick Bats - Local Kiln

Fine sand - Local

Cement Bag - Local Market

Aggregate for G.S.B - Matigara (Silliguri) by road up to site.

Bamboo - Local


Earth - Private land from 1000m lead.

(B) Rate - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.

Sanction of estimate is much needed for payment of the work which was already done.


J.E.
R.W.D
Kishanganj-2


A.E.
R.W.D
Kishanganj-2


R.E.E.
R.W.D
Kishanganj-2

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : L081 - T04 TO DHOBIBHITA (TRACK 81)
DISTRICT KISHANGANJ
DIVISION KISHANGANJ - 2
BLOCK THAKURGANJ
LENGTH OF ROAD (IN KM) 4.974

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	BRICK BAT	18.932
3	G.S.B.	0.000
4	SAND BAG	0.000
5	BAMBOO WORK	0.000
4	HUME PIPE	0.707
TOTAL COST OF PROJECT =		19.639
Add G.S.T. @ 12%		2.357
Add Seigniorage Fee @ 10 %		1.291
Total Cost of Restoration Work =		23.287

[Signature]
10/12/20
JE
RWD

[Signature]
11/12/20
AE
RWD

[Signature]
ER
RWD

Technically Approved for Rs. 23.287 Lacs. (Twenty three Lacs twenty eight thousand seven hundred) only.

[Signature]
20/12/20
अधीक्षण अभियन्ता
ग्रामीण कार्य विभाग
कार्य अंचल, किरानगंज