



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR REPAIRING OF ROAD

F.D.R. PART - A (2020)

L051-L050 TO DERAMARI (TRAVK51)

DETAILED ESTIMATE OF F.D.R. REPAIRING ROAD

ROAD LENGTH	0 TO 2100		
DISTRICT	KISHANGANJ		
BLOCK	THAKURGANJ		
DIVISION	KISHANGANJ - 2		
TOTAL LENGTH OF ROAD	2.100	KM	
TOTAL COST OF F.D.R. PART - A	Rs. 10.816	Lacs	
ADD G.S.T @ 12%	Rs. 1.298	Lacs	
Add Seigniorage Fee @ 10 %	Rs. 0.738	Lacs	
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 12.852	Lacs	

SUBMITTED BY
The Executive Engineer,
Works Division, Kishanganj - 2

Inspection Report for flood damage work

Date: 11.12.2020

1. Name of PIUs- Executive Engineers, RWD, Works Division, Kishanganj-2

2. Name of Block/Road- Thakurganj/

A. For Road

1. Damage Location/Chainage : 1125 m.

2. Damage Length : 63 m.

3. Nature of Damage : Crust washout and ditch

4. Details of Restoration :

i Material being used in Restoration : Brick Bat

ii Equipment/Tools being used in Restoration works: Trolley

iii Procedure taken up in Restoration works :

iv Restored Length : 63 m.

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

NA

Signature of JE/AE/EE
11/12/20

11/12/20
AK

12/12/20

Signature
(Name of Inspector)

TECHNICAL REPORT

Name of Work - FDR To Road From... LOS1-LOS0 TO Dehamari (Track 51)

Head - FDR

Estimated cost - ... 12.852 ... Lacs

The work done estimate has been framed for the restoration (motorable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

(A) Source of materials

Brick Bats - Local Kiln

Fine sand - Local

Cement Bag - Local Market


Aggregate for G.S.B - Matigara (Silliguri) by road up to site.

Bamboo - Local

Earth - Private land from 1000m lead.

(B) Rate - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.

Sanction of estimate is much needed for payment of the work which was already done.


J.E
R.W.D
Kishanganj-2


A.E
R.W.D
Kishanganj-2


E.E
R.W.D
Kishanganj-2

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : L051-L050 TO DERAMARI (TRAVK51)
DISTRICT KISHANGANJ
DIVISION KISHANGANJ - 2
BLOCK THAKURGANJ
LENGTH OF ROAD (IN KM) 2.100

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	BRICK BAT	10.816
3	G.S.B.	0.000
4	SAND BAG	0.000
5	BAMBOO WORK	0.000
4	HUME PIPE	0.000
TOTAL COST OF PROJECT =		10.816
Add G.S.T. @ 12%		1.298
Add Seigniorage Fee @ 10 %		0.738
Total Cost of Restoration Work =		12.852

Signature
10/12/20
JE
RWD

Signature
11/12/20
AE
RWD

Signature
21/12/20
EE
RWD

Technically Approved for Rs. 12.852 Lacs (Twelve Lacs Eighty five thousand two hundred) only.

Signature
20/12/20
अधीक्षक अभियन्ता
ग्रामीण कार्य विभाग
कार्य पंचल किशंगंज