

Inspection Report for Flood Damage Work

Date:- 21.09.2022

1. Name of PIUs:- E-E RWD Araria

2. Name of Block:- Araria

3. Name of Road:- patgaon charik to Sahasrimal tapra

A. For Road

1. Damage Location/Chainage :-

2. Damage Length :- 48.5 m

3. Nature of Damage :- breached & potholes

4. Details of Restoration Works:-

(i.) Material being used in Restoration Works:- B/B, E/C, bag, Boulders

(ii.) Equipments/Tools being used in Restoration works:- 303 Tractor

(iii.) Procedure taken up in Restoration works:-

(iv.) Restored Length :- 48.5 m

B. For Bridge

1. Damage Location/Chainage:-

2. Damage Length :-

3. Nature of Damage :-

4. Details of Restoration Works:-

(i.) Material being used in Restoration Works:-

(ii.) Equipments/Tools being used in Restoration works:-

(iii.) Procedure taken up in Restoration works:-

(iv.) Restored Length :

N/A


Signature of JE/AE/EE


Signature
(Name of Inspector)

प्रतिवेदन

पथ का नाम :- पट्टावा तोंड हें (वास्तविक)

कार्य का नाम :- PDR

में बाढ़ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।

संलग्न प्राक्कलन 10.06.2020 को प्रखण्ड में आयी भीषण बाढ़ से क्षतिग्रस्त पट्टावा तोंड


पथ में बाढ़ क्षतिग्रस्त मरम्मति मद से यातायात चालू करने हेतु तैयार किया गया है जिसकी प्राक्कलित लागत 2370045/- है।

रस्ता पथ का निर्माण 1412 योनान्तर्गत हुआ है एवं योजना अनुरक्षण पथ के कटे (क्षतिग्रस्त) अवधि में 1।


भाग में आवश्यकता अनुसार Hume Pipe, Bamboo, लोकल बालू एवं Brick Bats देने के बाद यातायात चालू कराया गया है। पथ के विभिन्न हिस्से में कराये गये कार्य का विवरणी स्वरूप से प्राक्कलन में दर्शाया गया है।

प्राक्कलन मदों का दर वर्तमान


अनुसूचित दर के अनुरूप है।



ज्नीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा,।



सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमण्डल,।



कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल,।

SUMMARY OF COST ESTIMATE FOR THE PROJECT		
NAME OF ROAD :-	Pategna Chowk to Sahsmal tak path	
DISTRICT :-	Araria	
BLOCK :-	Araria	
Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Labour for cutting 62mm to 75mm dia bamboo	16490.70
2	Nylon crate	307115.29
3	Supplying of EC bag, of local sand	307123.35
4	Supply and Carriage of brick bats	1466655.66
	SUB TOTAL COST =	2097385.00
	ADD GST @12% =	251686.20
	Add Labour cess @ 1% =	20973.85
	Add Contingency @ 1% =	0.00
	TOTAL (RS.) =	2370045

JE
4/9/20

A.E
21/9/20

E.E

S.E

T/A For Rs- 23,70,045/- (Rupees Twentythree Lacs Seventy thousand Forty Five Only.)

27/9/20

Bill of Quantity

NAME OF ROAD :-		Pategna Chowk to Sahsmal tak path			
DISTRICT :-		Araria			
BLOCK :-		Araria			
SL No.	DESCRIPTION OF ITEMS	QUANTITY	UNIT	RATE (Rs.)	AMOUNT (Rs.)
1	Labour for cutting 62 mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer- in -charge.	328.50	Mtr	50.20	16490.70
2	Labour for fitting empty cement bags with loocal sand, stitching the bags and placing in Nylon crate of size (1 m X 1 m X 1 m)with lead of 150 M including supply of sutli etc. at site in dry portion all complete as per approved design, specification and direction of E/I	322.06	Each	953.60	307115.29
3	Supplying of EC bag, filling of local sand stitching and placing in position as the direction of Engineer-in-charge.	8051.47	Each	38.15	307123.35
4	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.	683.75	Cum	2,145.02	1466655.66
A) SUB TOTAL =					2097385.00
TOTAL COST =					2097385

[Signature]
J.E

[Signature]
A.E

[Signature]
E.E

ESTIMATE FOR REPAIRING / RESTORATION/ MAKING MOTORABLE ROAD DAMAGED DURING FLOOD

NAME OF ROAD :-		Patana Chok to Subarn tal path									
DISTRICT :-		Karnali									
BLOCK :-		Karnali									
Sl. No.	DESCRIPTION OF ITEMS	Unit	No.	1(m)	2(m)	3(m)	4(m)	5(m)	6(m)	7(m)	AMOUNT (Rs.)
1	Labor for cutting 62 mm to 75 mm dia bamboo piles to size and making shores & driving by jet machine etc, all complete job as per specification & direction of Engineer-in-charge.	Mat.	2	25.5	4.50						
		Mat.			not apply						
											15,000.00
2	Labor for doing earth concrete works after road work, repairing the bridge and placing in Nylon canvas of size 10 m x 10 m. 1 m 1000) based on 1000 M repairing supply of 1000 etc. all work in city market all complete job as per approved design, specification and direction of E.I.	Q.M	2	25.5	1.50						
	Qty of Earth Works			212.75							
	Qty of Nylon Canvas = 1000 of 1000 x 10				1						
				205.50	1						
		Qty			not apply						
											15,000.00

Inspection Report for Flood Damage Work

Date:- 21.09.2018

1. Name of PUs:- EE PWD Araria

2. Name of Block:- Araria

3. Name of Road:- patipura to sokhara

A. For Road

1. Damage Location/Chainage :-

2. Damage Length :- 170 M

3. Nature of Damage :- Breached

4. Details of Restoration Works:-

(i.) Material being used in Restoration Works:- B/Bal

(ii.) Equipments/Tools being used in Restoration works:- Tractor, JCB

(iii.) Procedure taken up in Restoration works:-

(iv.) Restored Length :- 170 M

B. For Bridge

1. Damage Location/Chainage:-

2. Damage Length :-

3. Nature of Damage :-

4. Details of Restoration Works:-

(i.) Material being used in Restoration Works:-

(ii.) Equipments/Tools being used in Restoration works:-

(iii.) Procedure taken up in Restoration works:-

(iv.) Restored Length :

Signature of JE/AE/EE
21.9.18

Signature

(Name of Inspector)

प्रतिवेदन

1 का नाम :- मटेगाता चौक (र सहायता 73

2 का नाम :- FDR
में बाढ़ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।


लग्न प्राक्कलन 14.06.2020 को प्रखण्ड में आथी भीषण बाढ़ से क्षतिग्रस्त उपरोक्त

म.स. में बाढ़ क्षतिग्रस्त मरम्मति मद से यातायात चालू करने हेतु तैयार किया गया है
जसकी प्राक्कलित लागत 25 36 210 है।


क्षति पथ का निर्माण FDR योनान्तर्गत हुआ है एवं योजना अनुरक्षण
प्रवधि में है। पथ के कटे (क्षतिग्रस्त)

भाग में आवश्यकता अनुसार Hume Pipe, Bamboo, लोकल बालू एवं Brick Bats देने के बाद
यातायात चालू कराया गया है। पथ के विभिन्न हिस्से में कराये गये कार्य का विवरणी स्पष्ट
रूप से प्राक्कलन में दर्शाया गया है।


प्राक्कलन मदों का दर वर्तमान अनुसूचित दर के अनुरूप है।


21/9/20

कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा,


21/9/20

सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमण्डल,


21/9/20

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल,

SUMMARY OF COST ESTIMATE FOR THE PROJECT

NAME OF ROAD :-	Patogna Chowk to Sahamal tak path	
DISTRICT :-	Araria	
BLOCK :-	Araria	
Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Supply and Carriage of brick bats	2279885.39
	SUB TOTAL COST =	2279885.39
	ADD GST @12% =	273586.25
	Add Labour cess @ 1% =	22798.85
	Add Contingency @ 1% =	0.00
	TOTAL (RS.) =	2576270

[Signature]
J.E

[Signature]
A.E

[Signature]
E.E

S.E

T/A For Rs- 25,76,270/- (Rupees Twenty Five Lacs Seventy six thousand two hundred Seventy only.)

[Signature]
28/9/20

Bill of Quantity

NAME OF ROAD :-		Pategna Chowk to Sahamal tak path		
DISTRICT :-		Araria		
BLOCK :-		Araria		
Sl No.	DESCRIPTION OF ITEMS	QUANTITY	RATE (Rs.)	AMOUNT (Rs.)
1	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.	1062.88	2,145.02	2279885.39
		A) SUB TOTAL =		2279885.39
		TOTAL COST =		2279885

[Signature]
21.7.20
J.E

[Signature]
21/7/20
A.E

[Signature]
21/7/20
E.E

Inspection Report for Flood Damage Work

Date:-.....

1.Name of PIUs:- EG RWD Arara

2.Name of Block:- Arara

3.Name of Road:- Patangia Chauri to Sahaswarp

A. For Road

1.Damage Location/Chainage :- 302/Ch

2.Damage Length :- 170m

3.Nature of Damage :- breach

4.Details of Restoration Works:-

(i.)Material being used in Restoration Works:- Bricks Bala

(ii.)Equipments/Tools being used in Restoration works:- Truck 3 nos

(iii.)Procedure taken up in Restoration works:-

(iv.)Restored Length :- 170m

B. For Bridge

1. Damage Location/Chainage:-

2.Damage Length :-

3.Nature of Damage :-

4.Details of Restoration Works:-

(i.)Material being used in Restoration Works:-


(ii.)Equipments/Tools being used in Restoration works:-

(iii.)Procedure taken up in Restoration works:-

(iv.)Restored Length :

N/A


Signature of JE/AE/EE

 21/9/20 


Signature

(Name of Inspector)

प्रतिवेदन

पथ का नाम :- Satyana chowk to Sahasraal -Juni Path

कार्य का नाम :- RDR

में बाढ़ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।

संलग्न प्राक्कलन 14.06.2020 को प्रखण्ड में आयी भीषण बाढ़ से क्षतिग्रस्त 342047


..... में बाढ़ क्षतिग्रस्त मरम्मति मद से यातायात चालू करने हेतु तैयार किया गया है जिसकी प्राक्कलित लागत 1436100 है।

उक्त पथ का निर्माण MR योनान्तर्गत हुआ है एवं योजना अनुरक्षण अवधि में 1। पथ के कटे (क्षतिग्रस्त)

भाग में आवश्यकता अनुसार Hume Pipe, Bamboo, लोकल बालू एवं Brick Bats देने के बाद यातायात चालू कराया गया है। पथ के विभिन्न हिस्से में कराये गये कार्य का विवरणी स्पष्ट रूप से प्राक्कलन में दर्शाया गया है।

प्राक्कलन मदों का दर वर्तमान

अनुसूचित दर के अनुरूप है।



कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा,।



सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमण्डल,।



कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल,

SUMMARY OF COST ESTIMATE FOR THE PROJECT

NAME OF ROAD :-	Pategna Chowk to Sahsmal tak path	
DISTRICT :-	Araria	
BLOCK :-	Araria	
Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Supply and Carriage of brick bats	1536636.86
	SUB TOTAL COST =	1536636.86
	ADD GST @12% =	184396.42
	Add Labour cess @ 1% =	15366.37
	Add Contingency @ 1% =	0.00
	TOTAL (RS.) =	1736400

Red
24.7.20
J.E

W.S.
24/7/20
A.E

W.S.
24/7/20
E.E

S.E

T/A for Rs-17,36,400/- (Rupees Seventeen Lacs thirty six thousand four hundred only)

W.S.
23/7/20

Bill of Quantity

NAME OF ROAD :-		Pategna Chowk to Sahsmal lak path		
DISTRICT :-		Araria		
BLOCK :-		Araria		
Sl. No.	DESCRIPTION OF ITEMS	QUANTITY	RATE (Rs.)	AMOUNT (Rs.)
1	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.	716.38	2,145.02	1536636.86
		A) SUB TOTAL =		1536636.86
		TOTAL COST =		1536637

[Signature]
J.E

[Signature]
21/9/24
A.E

[Signature]
E.E