

प्रतिवेदन

कार्य का नाम:- राजा रामपुर बलानदी पक्की सड़क से राजा रामपुर
नजारा पश्चिम भाग तक पथ में अप्रत्याशित बाढ़/अतिवृष्टि 2020 से क्षतिग्रस्त पथ में
यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड- सरैया
वित्तीय वर्ष - 2020-21
प्राक्कलित राशि - Rs. 1398379/-

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 1398379 है, प्रखण्ड- सरैया में यातायात बहाली हेतु आपातकालीन मरम्मत के लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521 दिनांक 05.08.2020 द्वारा दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में Brick Bats & Local Sand भरकर पथ को चालू करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चलू अनुसूचित दर पर तैयार किया गया है। इसकी घटनोत्तर स्वीकृति अपेक्षित है।

18/12/20
कनीय अभियंता
सरैया

15/12/2020
सहायक अभियंता
सरैया

15.12.20
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल - मुजफ्फरनगर

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs- EXECUTIVE ENGINEER RWD (W) DIV. Muzaffarpur East-1
2 Name of Block/Road- Saraiya / Raja, Rampur Bayanadi Padeki
Sadak to Raja Rampur Naya to Padeki Shag
Jee.

A For Road

- 1 Damage Location/Chainage At every places
2 Damage Length 50.5 mtr
3 Nature of Damage Complete traffic Block due to Breach of road.
4 Details of Restoration Works-
i Material being used in Restoration Works- Brick Bat, local Sand
ii Equipments/Tools being used in Restoration Works- Road Roller, Tractor
iii Procedure Taken up in Restoration Works- Immediate Traffic Restoration
iv Restored Length 50.5 mtr

B. For Bridge

- 1 Damage Location/Chainage
2 Damage Length
3 Nature of Damage
4 Details of Restoration Works-
i Material being used in Restoration Works-
ii Equipments/Tools being used in Restoration Works-
iii Procedure Taken up in Restoration Works-
iv Restored Length

N/A

Signature of JE/ AE/ EE


Signature
(Name of Inspector)

GENERAL ABSTRACT

Name of Road Raja Rampur Baye Nadi Pakki Sadak to Raja Rampur Naya Tola Paschim Bhag Tak
District Muzaffarpur
Block Saraiya
Division Muzaffarpur East-1
Length of Road (in Km) 1.800 Km


Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
		0.000
1	Earthwork	13.685
1	Jhama metal	0.298
2	Sand Filling	0.000
3	Sand Bag	0.000
4	Bamboo Piles	13.984
	GRAND SUB TOTAL	13.984
TOTAL COST OF PROJECT IN LACS =		


JE
RWD


AE
RWD


EE
RWD

Technically approved for Rs. 1398400 = (Rs. Thirteen
lacs ninety eight thousand four hundred) only.


SE, RWD
Ward, Circle, Muzaffarpur

Sl. No.	SDB SL NO	MORD Ref. No	Description	Unit	QUANTITY	RATE	AMOUNT (in Rs.)
1		13.7 SoR Bihar Govt. (1985)	Jhama metal Labour for consolidation in Jhama metal by Road Roller in proper grade camber and super elevation dry and wet rolling including cost of running charge of roller diver and khalasi making and maintaining diversion light barrier - do - do- danger signal etc. all complete .	Cum	673.05		
			Appendix - I	Total	673.05	2033.34	1368539.49
2		11.20	Sand Filling Filling in foundation trenches as per drawing and technical specification Clause 305.3.9	Cum	65.650		
			Appendix - II	Total	65.65	454.53	29839.89
3		Ref. RCD SoR (12.9)	Sand bag Labour for Filling Sand Bag, Stitching and Placing etc. all complete as per specification and direction of E/I.	Nos	0		
			Appendix - III	Total	0.00	24.54	0.00
						SUB TOTAL =	1398379.38

5.12.2020
A.R

5.12.20
A.R