



# ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

## DETAILED PROJECT REPORT FOR REPAIRING OF ROAD

F.D.R. PART - A (2020)

L036 TO GAFFAR TOLA

### DETAILED ESTIMATE OF F.D.R. REPAIRING ROAD

|                                       |                |            |      |
|---------------------------------------|----------------|------------|------|
| ROAD LENGTH                           | 0 TO 1400      |            |      |
| DISTRICT                              | KISHANGANJ     |            |      |
| BLOCK                                 | THAKURGANJ     |            |      |
| DIVISION                              | KISHANGANJ - 2 |            |      |
| TOTAL LENGTH OF ROAD                  |                | 1.400      | KM   |
| TOTAL COST OF F.D.R. PART - A         |                | Rs. 21.059 | Lacs |
| ADD G.S.T @ 12%                       |                | Rs. 2.527  | Lacs |
| Add Seigniorage Fee @ 10 %            |                | Rs. 1.436  | Lacs |
| TOTAL COST OF RESTORATION WORK In Rs. |                | Rs. 25.022 | Lacs |

SUBMITTED BY  
The Executive Engineer,  
Works Division, Kishanganj - 2

## Inspection Report for flood damage work

Date: 11/12/2020

1. Name of PIUs- E.E., R.W.D. (W) Div. Kishanganj-2

2. Name of Block/Road- Thakurganj / 1036 to Gaffar tola.

### **A. For Road**

1. Damage Location/Chainage : 840M, 1150M

2. Damage Length : 145.60M

3. Nature of Damage : edge cutting shoulder

4. Details of Restoration :

i Material being used in Restoration

: Bamboo, Sandbags, Block bats.

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length : 145.60M

### **B. For Bridge**

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

M. A.

  
Signature of JE/AE/EE

  
11/12/2020  
AE

  
12/12/20

  
Signature

(Name of Inspector)

## TECHNICAL REPORT

Name of Work - FDR To Road From... L036 to Graftar Tola.....  
Head - FDR  
Estimated cost - ..... 25.022 Lacs

The work done estimate has been framed for the restoration (motorable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

**(A) Source of materials**

Brick Bats - Local Kiln  
Fine sand - Local  
Cement Bag - Local Market  
Aggregate for G.S.B - Matigara (Silliguri) by road up to site.  
Bamboo - Local  
Earth - Private land from 1000m lead.

**(B) Rate** - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.

Sanction of estimate is much needed for payment of the work which was already done.

Kishanganj  
11/12/20  
J.E  
R.W.D  
Kishanganj-2

Kishanganj  
11/12/20  
A.E  
R.W.D  
Kishanganj-2

Kishanganj  
12/12/20  
E.E  
R.W.D  
Kishanganj-2

**GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD**

NAME OF ROAD : L036 TO GAFFAR TOLA  
DISTRICT KISHANGANJ  
DIVISION KISHANGANJ - 2  
BLOCK THAKURGANJ  
LENGTH OF ROAD (IN KM) 1.400

| Sl. No.                          | ITEM OF WORK | AMOUNT<br>(LAKHS) |
|----------------------------------|--------------|-------------------|
| 1                                | EARTH WORK   | 0.000             |
| 2                                | BRICK BAT    | 14.026            |
| 3                                | G.S.B.       | 0.000             |
| 4                                | SAND BAG     | 4.798             |
| 5                                | BAMBOO WORK  | 2.234             |
| 4                                | HUME PIPE    | 0.000             |
| TOTAL COST OF PROJECT =          |              | 21.059            |
| Add G.S.T. @ 12%                 |              | 2.527             |
| Add Seigniorage Fee @ 10 %       |              | 1.436             |
| Total Cost of Restoration Work = |              | 25.022            |

*[Signature]*  
10/12/20  
JE  
RWD

*[Signature]*  
11/12/20  
AE  
RWD

*[Signature]*  
11/12/20  
EE  
RWD

Technically Approved for Rs. 25.022 Lacs (Twenty five Lacs two thousands two hundred) only.

*[Signature]*  
20/12/20  
अधीक्षक अभियन्ता  
ग्रामीण कार्य विभाग  
कार्य अंचल, किशनगंज