



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR REPAIRING OF ROAD

F.D.R. PART - A (2020)

T04 KE 15TH KM TO DALLEGAW ROAD

DETAILED ESTIMATE OF F.D.R. REPAIRING ROAD

ROAD LENGTH	0 TO 6000	
DISTRICT	KISHANGANJ	
BLOCK	THAKURGANJ	
DIVISION	KISHANGANJ - 2	
TOTAL LENGTH OF ROAD	6.000	KM
TOTAL COST OF F.D.R. PART - A	Rs. 1.655	Lacs
ADD G.S.T @ 12%	Rs. 0.199	Lacs
Add Seigniorage Fee @ 10 %	Rs. 0.107	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 1.961	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Kishanganj - 2

Inspection Report for flood damage work

Date: 12-12-2020

1. Name of PIUs- E.E, RWD(W) Div. Kishangang-2

2. Name of Block/Road- Thakurganj/ To 4 km 15 km To Ballegau Road.

A. For Road

1. Damage Location/Chainage : 5900M

2. Damage Length : 9.40M

3. Nature of Damage : crust washed out.

4. Details of Restoration :

i Material being used in Restoration

: Hume pipe, Bolek bats

ii Equipment/Tools being used in Restoration works:

: Tractor

iii Procedure taken up in Restoration works

:

iv Restored Length

: 9.40

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

:

ii Equipment/Tools being used in Restoration works:

:

iii Procedure taken up in Restoration works

:

iv Restored Length

:

} N.A.


Signature of JE/AE/EE


12/12/2020
AE


12/12/2020


Signature

(Name of Inspector)

TECHNICAL REPORT

Name of Work - FDR To Road From... To 4 KE 15th KM to Dallegaw Road,

Head - FDR

Estimated cost - 01.961 Lacs

The work done estimate has been framed for the restoration (motorable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

(A) Source of materials

Brick Bats - Local Kiln

Fine sand - Local

Cement Bag - Local Market


Aggregate for G.S.B - Matigara (Silliguri) by road up to site.

Bamboo - Local

Earth - Private land from 1000m lead.

(B) Rate - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.

Sanction of estimate is much needed for payment of the work which was already done.


J.E.
R.W.D
Kishanganj-2


A.E.
R.W.D
Kishanganj-2


E.E.
R.W.D
Kishanganj-2

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : T04 KE 15TH KM TO DALLEGAW ROAD
DISTRICT KISHANGANJ
DIVISION KISHANGANJ - 2
BLOCK THAKURGANJ
LENGTH OF ROAD (IN KM) 6.000

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	BRICK BAT	1.565
3	G.S.B.	0.000
4	SAND BAG	0.000
5	BAMBOO WORK	0.000
4	HUME PIPE	0.091
TOTAL COST OF PROJECT =		1.655
Add G.S.T. @ 12%		0.199
Add Seigniorage Fee @ 10 %		0.107
Total Cost of Restoration Work =		1.961

[Signature]
12/12/20
JE
RWD

[Signature]
12/12/20
AE
RWD

[Signature]
20/11/20
EE
RWD

Technically Approved For Rs. 1.961 Lacs. (One lac Ninty six thousand one hundred) only.

[Signature] 20/11/20
अधीक्षण अभियन्ता
ग्रामीण कार्य विभाग
कार्य अंशल, किशनगंज