



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR FDR



Name of the Road :-		SH-74 Bajrangi Ray Ke Ghar To Chak Ibrahim to Abuchak Masjid Tak	
DISTRICT		Muzaffarpur	
DIVISION		Muzaffarpur East-1	
BLOCK		Saraiya	
TOTAL LENGTH OF ROAD		:	1.410 KM
CONSTRUCTION COST		:	4.917 Lac

Submitted By :-
Executive Engineer
RWD Work Division Muzaffarpur East-1

प्रतिवेदन

कार्य का नाम:- SH-74 Bajjammaji Ray ke Gehar to Chak Ibrahim
to Abnehaq Masjid ke.

पथ में अप्रत्याशित बाढ़/अतिवृष्टि 2020 से क्षतिग्रस्त पथ में यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड- सरैया
वित्तीय वर्ष - 2020-21
प्राक्कलित राशि - Rs. 491780=

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 491780= है,
प्रखण्ड- सरैया में यातायात बहाली हेतु आपातकालीन मरम्मत के लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521 दिनांक 05.08.2020 द्वारा दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में Brick Bats & Local Sand भरकर पथ को चालू करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चलू अनुसूचित दर पर तैयार किया गया है। इसकी घटनोत्तर स्वीकृति अपेक्षित है।

88/का/सा/प्र/म
कनीय अभियंता
सरैया

91/का/सा/प्र/म
5.12.2020
सहायक अभियंता
सरैया

91/का/सा/प्र/म
15.12.20
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल - मुन्नापुरी

Inspection Report for Flood Damage Work

Date

1. Name of PIUs- EXECUTIVE ENGINEER RWD (W) DIV. Muzaffarpur East-1
2. Name of Block/Road- Saraiya / SH-74 Bajrangsi Ray ko Gehar to Chak Ibrahim to Abnehak road/jid talak.

A For Road

1. Damage Location/Chainage ² ~~At many places~~ Ch. 1210 to 1235
2. Damage Length : 25.00 Mtr
3. Nature of Damage Complete traffic block due to breach of road from flood water.
4. Details of Restoration Works-
 - i. Material being used in Restoration Works- Bangle Ball, local Sand
 - ii. Equipments/Tools being used in Restoration Works- static roller, Tractor Mammal
 - iii. Procedure Taken up in Restoration Works- Traffic Restoration immediately after flood
 - iv. Restored Length 25.0000 Mtr


B. For Bridge

N/A

1. Damage Location/Chainage
2. Damage Length
3. Nature of Damage
4. Details of Restoration Works-
 - i. Material being used in Restoration Works-
 - ii. Equipments/Tools being used in Restoration Works-
 - iii. Procedure Taken up in Restoration Works-
 - iv. Restored Length

N/A


Signature of JE/ AE/ EE


Signature
(Name of Inspector)

GENERAL ABSTRACT

Name of Road SH-74 Bajrangi Ray Ke Ghar To Chak Ibrahim to Abuchak Masjid Tak

District Muzaffarpur


Block Saraiya

Division Muzaffarpur East-1

Length of Road (in Km) 1.410 Km


Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Earthwork	0.000
1	Jhama metal	4.804
2	Sand Filling	0.114
3	Sand Bag	0.000
4	Bamboo Piles	0.000
	GRAND SUB TOTAL	4.917
TOTAL COST OF PROJECT IN LACS =		4.917


JE
RWD


AE
RWD


EE
RWD

Technically approved for Rs. 491700 = 00 (Rs. Four lakhs
nearly one thousand Seven hundred nearly.


SE, RWD
Muzaffarpur

Sl. No.	SDB SL NO	MORD Ref. No	Description	Unit	QUANTITY	RATE	AMOUNT (in Rs.)
1		13.7 SoR Bihar Govt. (1985)	Jhama metal Labour for consolidation in Jhama metal by Road Roller in proper grade camber and super elevation dry and wet rolling including cost of running charge of roller diver and khalasi making and maintaining diversion light barrier - do - do- danger signal etc. all complete .	Cum	236.25		
			Appendix - I				
				Total	236.25	2033.34	480376.58
2		11.20	Sand Filling Filling in foundation trenches as per drawing and technical specification Clause 305.3.9				
			Appendix - II	Cum	25.000		
				Total	25.00	454.53	11363.25
3		Ref. RCD SoR (12.9)	Sand bag Labour for Filling Sand Bag, Stitching and Placing etc. all complete as per specification and direction of E/I.				
			Appendix - III	Nos	0		
				Total	0.00	24.54	0.00
						SUB TOTAL =	491739.83

1

 5.12.2020
 A.12

 15.12.20