



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR REPAIRING OF ROAD

F.D.R. PART - A (2020)

BHUTIJHARI TO BHEL TOPI

DETAILED ESTIMATE OF F.D.R. REPAIRING ROAD

ROAD LENGTH	0 TO 950	
DISTRICT	KISHANGANJ	
BLOCK	THAKURGANJ	
DIVISION	KISHANGANJ - 2	
TOTAL LENGTH OF ROAD	0.950	KM
TOTAL COST OF F.D.R. PART - A	Rs. 7.627	Lacs
ADD G.S.T @ 12%	Rs. 0.915	Lacs
Add Seigniorage Fee @ 10 %	Rs. 1.291	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 9.833	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Kishanganj - 2

Inspection Report for flood damage work

Date: 12.12.2020

1. Name of PIUs- E.E. RWD (WORKS) Division Kishanganj-2
2. Name of Block/Road- Thakurganj / Bhulighari to Bet Bhel topi

A. For Road

1. Damage Location/Chainage : 775 m
2. Damage Length : ~~36.8 m~~ 121.8 m
3. Nature of Damage : Both bank cutting
4. Details of Restoration :
i Material being used in Restoration *locat* : Local sand and Brick Bats
ii Equipment/Tools being used in Restoration works: Tractor
iii Procedure taken up in Restoration works :
iv Restored Length : ~~36.8 m~~ 121.8 m

B. For Bridge

1. Damage Location/Chainage :
2. Damage Length :
3. Nature of Damage :
4. Details of Restoration :
i Material being used in Restoration :
ii Equipment/Tools being used in Restoration works :
iii Procedure taken up in Restoration works :
iv Restored Length :

Amish
12/12/20
Signature of JE/AE/EE

AE
12/12/20
AE

[Signature]
Signature

(Name of Inspector)

30
12.12.20

TECHNICAL REPORT

Name of Work - FDR To Road From Bhutikhari to Bhel Topi
Head - FDR
Estimated cost - 09.8.33 .. Lacs


The work done estimate has been framed for the restoration (motarable) of traffic for the above road which was damage during the year 2020-2021 flash flood.


(A) Source of materials


Brick Bats - Local Kiln
Fine sand - Local
Cement Bag - Local Market
Aggregate for G.S.B - Matigara (Silliguri) by road up to site.
Bamboo - Local
Earth - Private land from 1000m lead.

(B) Rate - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.

Sanction of estimate is much needed for payment of the work which was already done.


J.E
R.W.D
Kishanganj-2


A.E
R.W.D
Kishanganj-2


R.W.D
Kishanganj-2

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : BHUTIJHARI TO BHEL TOPI
DISTRICT KISHANGANJ
DIVISION KISHANGANJ - 2
BLOCK THAKURGANJ
LENGTH OF ROAD (IN KM) 0.950

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	LOCAL SAND FILLING	5.717
2	BRICK BAT	1.910
3	G.S.B.	0.000
4	SAND BAG	0.000
5	BAMBOO WORK	0.000
4	HUME PIPE	0.000
TOTAL COST OF PROJECT =		7.627
Add G.S.T. @ 12%		0.915
Add Seigniorage Fee @ 10 %		1.291
Total Cost of Restoration Work =		9.833

Amulya
12/12/20
JE
RWD

Amulya
12/12/20
AE
RWD

Bnd
12-12-20
EE
RWD

Technically Approved For Rs. 9.833 Lacs. (Nine Lac eighty three thousand three hundred) only.

Amulya
20/12/20
अधीक्षण अभियन्ता
ग्रामीण कार्य विभाग
कार्य अंचल, किशनगंज