



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR REPAIRING OF ROAD

F.D.R. PART - A (2020)

T01 THAKURGANJ TO KHARUDAH

DETAILED ESTIMATE OF F.D.R. REPAIRING ROAD

ROAD LENGTH	0 TO 28000		
DISTRICT	KISHANGANJ		
BLOCK	THAKURGANJ		
DIVISION	KISHANGANJ - 2		
TOTAL LENGTH OF ROAD		28.000	KM
TOTAL COST OF F.D.R. PART - A		Rs. 31.835	Lacs
ADD G.S.T @ 12%		Rs. 3.820	Lacs
Add Seigniorage Fee @ 10 %		Rs. 2.135	Lacs
TOTAL COST OF RESTORATION WORK In Rs.		Rs. 37.790	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Kishanganj - 2

Inspection Report for flood damage work

Date: 12.12.2020

1. Name of PIUs- E.E. RWD (Works) Division Kishanganj-2

2. Name of Block/Road- Thakurganj/TO1 Thakurganj to Kharudah

A. For Road

1. Damage Location/Chainage : 1450 m to 5500 m

2. Damage Length : 87.6 m

3. Nature of Damage : Flood damage ditch.

4. Details of Restoration :
i Material being used in Restoration : Brick Bats and RCC Pipe 1000 mm

ii Equipment/Tools being used in Restoration works: Tractor

iii Procedure taken up in Restoration works :

iv Restored Length : 87.6 m

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :


4. Details of Restoration :


i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :


Signature of JE/AE/EE


AE


12/12/20


Signature

(Name of Inspector)

TECHNICAL REPORT

Name of Work - FDR To Road From... Toi Thakirganj to Kharudah

Head - FDR

Estimated cost - 37.790 Lacs

The work done estimate has been framed for the restoration (matarable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

(A) Source of materials

Brick Bats - Local Kiln

Fine sand - Local

Cement Bag - Local Market

Aggregate for G.S.B - Matigara (Silliguri) by road up to site.


Bamboo - Local

Earth - Private land from 1000m lead.

(B) Rate - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.

Sanction of estimate is much needed for payment of the work which was already done.


J.E.
R.W.D
Kishanganj-2


A.E.
R.W.D
Kishanganj-2


E.E.
R.W.D
Kishanganj-2

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : T01 THAKURGANJ TO KHARUDAH
DISTRICT KISHANGANJ
DIVISION KISHANGANJ - 2
BLOCK THAKURGANJ
LENGTH OF ROAD (IN KM) 28.000

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	BRICK BAT	31.310
3	G.S.B.	0.000
4	SAND BAG	0.000
5	BAMBOO WORK	0.000
4	HUME PIPE	0.525
TOTAL COST OF PROJECT =		31.835
Add G.S.T. @ 12%		3.82
Add Seigniorage Fee @ 10 %		2.135
Total Cost of Restoration Work =		37.790

Amgr.
12/12/2020
JE
RWD

Amr
12/12/2020
AE
RWD

30/12/2020
EE
RWD

Technically Approved For Rs. 37.790 Lacs (Thirty Seven Lacs Seventy nine thousands) only.

30/12/2020
अधीक्षण अभियन्ता
ग्रामीण कार्य विभाग
कार्य प्रचार, किशनगंज