

Inspection Report for Flood Damage Work

Date:- 21.07.2018

1.Name of PIUs:- EE RWD Area

2.Name of Block:- Area

3.Name of Road:- Hazaripur to Bhagwanpur

A. For Road

1.Damage Location/Chainage :-

2.Damage Length :- 47M

3.Nature of Damage :- breach

4.Details of Restoration Works:-

(i.)Material being used in Restoration Works:- local sand, bamboo, 3/4" B&S, E/c bag

(ii.)Equipments/Tools being used in Restoration works:- Trucks, 3 cr

(iii.)Procedure taken up in Restoration works:-

(iv.)Restored Length :- 47M

B. For Bridge

1. Damage Location/Chainage:-

2.Damage Length :-

3.Nature of Damage :-

4.Details of Restoration Works:-


(i.)Material being used in Restoration Works:-

(ii.)Equipments/Tools being used in Restoration works:-

(iii.)Procedure taken up in Restoration works:-

(iv.)Restored Length :

N/A



Signature of JE/AE/EE



(Name of Inspector)

प्रतिवेदन

पथ का नाम :- हसनपुर से जगजगद

कार्य का नाम :- FDR

में बाढ़ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।


संलग्न प्राक्कलन 10.06.2020 को प्रखण्ड में आयी भीषण बाढ़ से क्षतिग्रस्त उपर्युक्त


पथ में बाढ़ क्षतिग्रस्त मरम्मत मद से यातायात चालू करने हेतु तैयार किया गया है जिसकी प्राक्कलित लागत 1098786/- है।


उक्त पथ का निर्माण योनान्तर्गत हुआ है एवं योजना अनुरक्षण अवधि में 10/11/20

भाग में आवश्यकता अनुसार Hume Pipe, Bamboo, लोकल बालू एवं Brick Bats देने के बाद यातायात चालू कराया गया है। पथ के विभिन्न हिस्से में कराये गये कार्य का विवरणी स्पष्ट रूप से प्राक्कलन में दर्शाया गया है।

प्राक्कलन मदों का दर वर्तमान अनुसूचित दर के अनुरूप है।


उप-विवरण,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा,।


सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमण्डल,।


कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल,।

SUMMARY OF COST ESTIMATE FOR THE PROJECT		
NAME OF ROAD :-	Hasanpur to Bhagmohbat	
DISTRICT :-	Araria	
BLOCK :-	Araria	
Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Filling of local sand	79238.90
2	Labour for cutting 62mm to 75mm dia bamboo	1807.20
3	Supplying of EC bag, of local sand	18174.97
4	Supply and Carriage of brick bats	873156.16
	SUB TOTAL COST =	972377.22
	ADD GST @12% =	116685.27
	Add Labour cess @ 1% =	9723.77
	Add Contingency @ 1% =	0.00
	TOTAL (RS.) =	1098786

J.E
21.7.20

A.E
21/9/20

E.E
21/9/20


S.E


T/A for Rs - 10,98,786.00 (Rupees Ten Lacs Ninety Eight thousand Seven Hundred eighty six Only.)

23/11/20

Bill of Quantity

NAME OF ROAD :-		Hasanpur to Bhagmohbat		
DISTRICT :-		Araria		
BLOCK :-		Araria		
Sl. No.	DESCRIPTION OF ITEMS	QUANTITY	RATE (Rs.)	AMOUNT (Rs.)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge	126.40	626.89	79238.90
2	Labour for cutting 62 mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer- in -charge.	36.00	50.20	1807.20
3	Supplying of EC bag, filling of local sand stitching and placing in position as the direction of Engineer-in-charge.	476.47	38.15	18174.97
4	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.	407.06	2,145.02	873156.16
		A) SUB TOTAL =		972377.22
		TOTAL COST =		972377


J.E


A.E


E.E

SI. No.	DESCRIPTION OF ITEMS	Unit	Nos.	L(m)	B(m)	D(m)	QUANTITY	RATE (Rs.)	AMOUNT (Rs.)
2	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge								
		cum	1	4.50	4.00	2.25	40.50		
		cum	1	4.00	3.50	1.85	25.90		
		cum	1	8.00	3.00	2.50	60.00		
		cum	total qty :-				126.40	626.89	79238.90
3	Labour for cutting 62 mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer- in -charge.								
			1	8.00	4.50		36.00		
			0	27.00	4.50		0.00		
	Mtr.	total qty:-					36.00	50.20	1,807.20

Sl. No.	DESCRIPTION OF ITEMS	Unit	Nos.	L(m)	B(m)	D(m)	QUANTITY	RATE (Rs.)	AMOUNT (Rs.)
6	Supplying of EC bag, filling of local sand stitching and placing in position as the direction of Engineer-in-charge.								
		cum	1	8	0.90	2.25	16.20		
	Total No of E C Bags(3.4cum=100bags) =			16.20	/	0.034	476.47		
7	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.	Each		Say No of Bage :-			476	38.15	18174.971
		cum	1	12.00	(6.50+5.0)/2	(1.250+1.50)/2	94.88		
		cum	1	25.50	5.00	(2.50+1.85)/2	277.31		
		cum	1	5.00	5.00	(0.850+0.700)/2	19.38		
		cum	1	5.00	4.00	(0.850+0.700)/2	15.50		
		cum		total qty :-			407.06	2,145.02	873156.16

Sl. No.	DESCRIPTION OF ITEMS	Unit	Nos.	L(m)	B(m)	D(m)	QUANTITY	RATE (Rs.)	AMOUNT (Rs.)
							A) SUB TOTAL =		972377.22
							TOTAL COST =		972377.22
	<i>Sub. Engineer</i> Junior Engineer <i>Asstt. Engineer</i> Asstt. Engineer <i>Executive Engineer</i> Executive Engineer								

S E
Kishanganj