

Inspection Report for Flood Damage Work

Date:-.....

1.Name of PIUs:-

2.Name of Block:-

3.Name of Road:- Main drive to road-14

A. For Road

1.Damage Location/Chainage :- 2nd / 4

2.Damage Length :- 55 m

3.Nature of Damage :- breach

4.Details of Restoration Works:-

(i.)Material being used in Restoration Works:- Bunker, Elchays B/Det, C. 13

(ii.)Equipments/Tools being used in Restoration works:- Tractor, JCB

(iii.)Procedure taken up in Restoration works:-

(iv.)Restored Length :- 55 m

B. For Bridge

1. Damage Location/Chainage:-

2.Damage Length :-

3.Nature of Damage :-

4.Details of Restoration Works:-


(i.)Material being used in Restoration Works:-

(ii.)Equipments/Tools being used in Restoration works:-

(iii.)Procedure taken up in Restoration works:-

(iv.)Restored Length :

N/A


Signature of JE/AE/EE


Signature

(Name of Inspector)

प्रतिवेदन

पथ का नाम :- Manty chowk to Malanpur

कार्य का नाम :- FDR

में बाढ़ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।


संलग्न प्राक्कलन 10.06.2020 को प्रखण्ड में आयी भीषण बाढ़ से क्षतिग्रस्त 21/9/20.....


पथ में बाढ़ क्षतिग्रस्त मरम्मत मद से यातायात चालू करने हेतु तैयार किया गया है जिसकी प्राक्कलित लागत 43680751..... है।


उक्त पथ का निर्माण FDR..... योनान्तर्गत हुआ है एवं योजना अनुरक्षण अवधि में है। पथ के कटे (क्षतिग्रस्त)

भाग में आवश्यकता अनुसार Hume Pipe, Bamboo, लोकल बालू एवं Brick Bats देने के बाद यातायात चालू कराया गया है। पथ के विभिन्न हिस्से में कराये गये कार्य का विवरणी स्पष्ट रूप से प्राक्कलन में दर्शाया गया है।

प्राक्कलन मदों का दर वर्तमान अनुसूचित दर के अनुरूप है।


कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा, अरुण।


सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमण्डल, अरुण।


कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, अरुण।

SUMMARY OF COST ESTIMATE FOR THE PROJECT

NAME OF ROAD :-	Mantu Chowk to Madanpur	
DISTRICT :-	Araria	
BLOCK :-	Araria	
Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Labour for cutting 62mm to 75mm dia bamboo	14683.50
2	Supplying of EC bag, of local sand	108544.96
3	Supply and Carriage of brick bats	252039.55
4	Granular Sub-base	3490284.99
	SUB TOTAL COST =	3865553.00
	ADD GST @12% =	463866.36
	Add Labour cess @ 1% =	38655.53
	Add Contingency @ 1% =	0.00
	TOTAL (RS.) =	4368075

[Signature]
J.E

[Signature]
A.E

[Signature]
E.E

S.E

T/A for Rs- 4368075:- (Fourty three thousand Sixty Eight thousand Seventy five only)

[Signature]
28/11/20

BMI of Quantity

NAME OF ROAD :-

Manlu Chowk to Madanpur


DISTRICT :-

SUPAUL

BLOCK :-

CHHATAPUR

Sl. No.	DESCRIPTION OF ITEMS	QUANTITY	RATE (Rs.)	AMOUNT (Rs.)
1	Labour for cutting 62 mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer- in -charge.	292.50	50.20	14683.50
2	Supplying of EC bag, filling of local sand stitching and placing in position as the direction of Engineer-in-charge.	2845.59	38.15	108544.96
3	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.	117.50	2,145.02	252039.55
4	Granular Sub-base with Well Graded Material (Table 400.1)	1038.81	3,359.90	3490284.99
		A) SUB TOTAL =		3865553.00
		TOTAL COST =		3865553


J.E


A.E


E.E

ESTIMATE FOR REPAIRING / RESTORATION/ MAKING MOTORABLE ROADS DAMAGED DURING FLOOD

NAME OF ROAD :-		Mantu Chowk to Madanpur							
DISTRICT :-		Araria							
BLOCK :-		Araria							
Sl. No.	DESCRIPTION OF ITEMS	Unit	Nos.	L(m)	B(m)	D(m)	QUANTITY	RATE (Rs.)	AMOUNT (Rs.)
1	Labour for cutting 62 mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer- in -charge.								
	River Portion 1st km		1	45.00	4.50		202.50		
	2nd km		2	10.00	4.50		90.00		
		Mtr.		total qty:-			292.50	50.20	14,683.50

2	Supplying of EC bag, filling of local sand stitching and placing in position as the direction of Engineer-in-charge.									
	River Portion 1st km	cum	1	45.00	0.90	1.50	60.75			
	2nd km	cum	2	10.00	0.90	2.00	36.00			
	Total No of E C Bags(3.4cum =100 Bags) =			96.75	/	0.034	2845.59			
		Each	Say No of Bage :-				2846	38.15	108544.96	
3	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.									
	River Portion 1st km	cum	1	45.00	1.50	1.00	67.50			
	2nd km	cum	2	10.00	2.00	1.25	50.00			
		cum	total qty :-				117.50	2,145.02	252039.55	

Granular Sub-base with Well Graded Material (Table 400.1)

4 Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.

1st km	cum	1	45	3.75	0.15	25.3125	
1st km	cum	1	30	3.5	0.15	15.75	
1st km	cum	1	72	3.5	0.15	37.8	
1st km	cum	1	30	3.5	0.15	15.75	
2nd km	cum	1	40	3.5	0.15	21	
2nd km	cum	1	50	3.5	0.15	26.25	
2nd km	cum	1	65	3.5	0.15	34.125	
2nd km	cum	1	40	3.5	0.15	21	
3rd km	cum	1	30	3.5	0.15	15.75	
3rd km	cum	1	80	3.5	0.15	42	
3rd km	cum	1	70	3.5	0.15	36.75	
3rd km	cum	1	30	3.5	0.15	15.75	
3rd km	cum	1	20	3.5	0.15	10.5	
Pot Measurement (Area As Per Annexure)	cum					721.07	
			total qty :-			1038.81	
	cum					1038.81	3,359.90
						A) SUB TOTAL =	
							3865553.00

