



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR REPAIRING OF ROAD

F.D.R. PART - A (2020)

T04 - DALLEGAON KA 15TH KM RCC BRIDGE PAR
DALEGAON TOLA KE BAGAL ME DALLEGAON RAOD

DETAILED ESTIMATE OF F.D.R. REPAIRING ROAD

ROAD LENGTH	0 TO 26.44		
DISTRICT	KISHANGANJ		
BLOCK	THAKURGANJ		
DIVISION	KISHANGANJ - 2		
TOTAL LENGTH OF ROAD	0.026	KM	
TOTAL COST OF F.D.R. PART - A	Rs. 4.686	Lacs	
ADD G.S.T @ 12%	Rs. 0.562	Lacs	
Add Seigniorage Fee @ 10 %	Rs. 0.073	Lacs	
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 5.320	Lacs	

SUBMITTED BY
The Executive Engineer,
Works Division, Kishanganj - 2

Inspection Report for flood damage work

Date: 12-12-2020

1. Name of PIUs- E. E. R. W. D (W) Div - Kishanganj-2

2. Name of Block/Road- Thakurganj / To4- Dallegaroon ke 15th km RCC bridge.

A. For Road

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

N.A.

B. For Bridge

1. Damage Location/Chainage : 0.0 KM

2. Damage Length : 75.0M

3. Nature of Damage : Flank washed out duringe.

4. Details of Restoration :

i Material being used in Restoration

: Local sand & brick bats

ii Equipment/Tools being used in Restoration works:

: Tractor

iii Procedure taken up in Restoration works :

iv Restored Length

: 75.0M

Signature of JE/AE/EE

Signature
12/12/20

Signature
12/12/20
AE

Signature
12/12/20

Signature

(Name of Inspector)

TECHNICAL REPORT

Name of Work - FDR To Road From... *Tola - Dallegaon ka 15th km RCE Bridge Par*
Head - FDR *Dallegaon Tola ke Bagal me Dallegaon Road tak*
Estimated cost - *05.320* ... Lacs

The work done estimate has been framed for the restoration (motorable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

(A) Source of materials

Brick Bats - Local Kiln
Fine sand - Local
Cement Bag - Local Market
Aggregate for G.S.B - Matigara (Silliguri) by road up to site.
Bamboo - Local
Earth - Private land from 1000m lead.

(B) Rate - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.

Sanction of estimate is much needed for payment of the work which was already done.

[Signature]
11/12/20
J.E
R.W.D
Kishanganj-2

[Signature]
11/12/20
A.E
R.W.D
Kishanganj-2

[Signature]
11/12/20
E.E
R.W.D
Kishanganj-2

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : T04 - DALLEGAON KA 15TH KM RCC BRIDGE PAR DALEGAON TOLA KE
BAGAL ME DALLEGAON RAOD TAK
DISTRICT KISHANGANJ
DIVISION KISHANGANJ - 2
BLOCK THAKURGANJ
LENGTH OF ROAD (IN KM) 0.026

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	3.619
2	BRICK BAT	1.066
3	G.S.B.	0.000
4	SAND BAG	0.000
5	BAMBOO WORK	0.000
4	HUME PIPE	0.000
TOTAL COST OF PROJECT =		4.686
Add G.S.T. @ 12%		0.562
Add Seigniorage Fee @ 10 %		0.073
Total Cost of Restoration Work =		5.320

[Signature]
12/12/20
JE
RWD

[Signature]
12/12/20
AE
RWD

[Signature]
12.12.20
EE
RWD

Technically Approved for Rs. 5.320 Lacs (five Lacs thirty two thousand) only.

[Signature] 30/12/20
अधीक्षण अभियन्ता
ग्रामीण कार्य विभाग
कार्य अंचल, किशनगंज