



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR REPAIRING OF ROAD

F.D.R. PART - A (2020)

L085- T04 TO KASIBARI (TRACK 85)

DETAILED ESTIMATE OF F.D.R. REPAIRING ROAD

ROAD LENGTH	0 TO 1721	
DISTRICT	KISHANGANJ	
BLOCK	THAKURGANJ	
DIVISION	KISHANGANJ - 2	
TOTAL LENGTH OF ROAD	1.721	KM
TOTAL COST OF F.D.R. PART - A	Rs. ^{23.65} 58.958	Lacs
ADD G.S.T @ 12%	Rs. ^{2.838} 7.075	Lacs
Add Seigniorage Fee @ 10 %	Rs. ^{0.314} 0.769	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. ^{26.802} 66.802	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Kishanganj - 2

Inspection Report for flood damage work

Date: 11.12.2020

1. Name of PIUs- E.E, RWD (W) Div. Kishanganj-2

2. Name of Block/Road- Thakurganj / 1085-704 to Kajibari (Trunk 85)

A. For Road

1. Damage Location/Chainage : 200M, 1040M, 1350M, 1420M

2. Damage Length : 267.60M

3. Nature of Damage : Révet Along Road Protection and flume washed out.

4. Details of Restoration :

i Material being used in Restoration

: Bamboo, sand bags, Borek bags, sand filling.

ii Equipment/Tools being used in Restoration works: Tractor & JCB,

iii Procedure taken up in Restoration works :

iv Restored Length : 267.60M

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

N.A.

Signature of JE/AE/EE

[Signature]
11/12/2020
AE

[Signature]
Signature
(Name of Inspector)

TECHNICAL REPORT

Name of Work - FDR To Road From LO85 - To 6 to Kasibari (Track 85).
Head - FDR
Estimated cost - 26.802 Lacs

The work done estimate has been framed for the restoration (motarable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

(A) Source of materials

Brick Bats - Local Kiln

Fine sand - Local

Cement Bag - Local Market


Aggregate for G.S.B - Matigara (Silliguri) by road up to site.


Bamboo - Local


Earth - Private land from 1000m lead.

(B) Rate - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.

Sanction of estimate is much needed for payment of the work which was already done.


J.E.
R.W.D
Kishanganj-2


A.E.
R.W.D
Kishanganj-2


E.E.
R.W.D
Kishanganj-2

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : L085- T04 TO KASIBARI (TRACK 85)
 DISTRICT KISHANGANJ
 DIVISION KISHANGANJ - 2
 BLOCK THAKURGANJ
 LENGTH OF ROAD (IN KM) 1.721

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	BRICK BAT	49.565
3	G.S.B.	0.000
4	SAND BAG	4.319
5	BAMBOO WORK	5.075
4	HUME PIPE	0.000
TOTAL COST OF PROJECT =		68.958 23.65
Add G.S.T. @ 12%		7.075 2.838
Add Seigniorage Fee @ 10 %		9.769 0.317
Total Cost of Restoration Work =		66.802 26.802

[Signature]
 10/12/20
 JE
 RWD

[Signature]
 11/12/2020
 AE
 RWD

[Signature]
 12/12/20
 EE
 RWD

Technically Approved for Rs. 66.802 Lacs (Twenty Six Lacs eighty thousand two hundred) only.

[Signature]
 अधीक्षक अभियन्ता
 ग्रामीण कार्य विभाग
 कार्य अंचल, किरानगंज