



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR REPAIRING OF ROAD

F.D.R. PART - A (2020)

T03 PAUAKHALI BAZER TO SIMALBARI (TRACK4)

DETAILED ESTIMATE OF F.D.R. REPAIRING ROAD

ROAD LENGTH	0 TO 2861	
DISTRICT	KISHANGANJ	
BLOCK	THAKURGANJ	
DIVISION	KISHANGANJ - 2	
TOTAL LENGTH OF ROAD	2.861	KM
TOTAL COST OF F.D.R. PART - A	^{26.25} Rs. 70.187	Lacs
ADD G.S.T @ 12%	^{3.15} Rs. 8.422	Lacs
Add Seigniorage Fee @ 10 %	Rs. 1.258 0.47	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 79.867 29.867	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Kishanganj - 2

Inspection Report for flood damage work

Date: 12/12/2020

1. Name of PIUs- E.E, RWD (W) Div. - Kishanganj-2

2. Name of Block/Road- Thakurganj / To Pawa Khali Bazar to Simulbari

A. For Road

1. Damage Location/Chainage : 1056M, 1988M

2. Damage Length : 193.40 + 37.20M

3. Nature of Damage : crust & shoulder damage on the river

4. Details of Restoration :

i Material being used in Restoration : Bamboo, sandbags, local sand.

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length : 230.60M

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :


i Material being used in Restoration :


ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

} N.A.


Signature of JE/AE/EE


12/12/2020
AE


12/12/2020


Signature

(Name of Inspector)

TECHNICAL REPORT

Name of Work - FDR To Road From... To 3 Pawakhali Bazar to Simabari
(Track 4)
Head - FDR
Estimated cost - 29.867 Lacs


The work done estimate has been framed for the restoration (motorable) of traffic for the above road which was damage during the year 2020-2021 flash flood.


(A) Source of materials


Brick Bats - Local Kiln
Fine sand - Local
Cement Bag - Local Market
Aggregate for G.S.B - Matigara (Silliguri) by road up to site.
Bamboo - Local
Earth - Private land from 1000m lead.

(B) Rate - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.

Sanction of estimate is much needed for payment of the work which was already done.


J.E.
R.W.D
Kishanganj-2


A.E.
R.W.D
Kishanganj-2


E.E.
R.W.D
Kishanganj-2

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : T03 PAUAKHALI BAZER TO SIMALBARI (TRACK4)
DISTRICT KISHANGANJ
DIVISION KISHANGANJ - 2
BLOCK THAKURGANJ
LENGTH OF ROAD (IN KM) 2.861

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK Local sand	50.581
2	BRICK BAT	18.446
3	G.S.B.	0.000
4	SAND BAG	0.000
5	BAMBOO WORK	1.160
4	HUME PIPE	0.000
TOTAL COST OF PROJECT =		70.187 26.5
Add G.S.T. @ 12%		8.422 3.15
Add Seigniorage Fee @ 10 %		4.268 0.47
Total Cost of Restoration Work =		79.867 29.867

[Signature]
12/12/2020
JE
RWD

[Signature]
12/12/2020
AE
RWD

[Signature]
12/12/2020
EE
RWD

Technically Approved Rs. 79.867 Lacs (^{Twenty} ~~Seventy~~ Nine Lacs eighty six thousand seven hundred) only.

[Signature]
30/11/20
अधीक्षक अभियन्ता
ग्रामीण कार्य विभाग
कार्य अंचल, किशनगंज