



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR REPAIRING OF ROAD

F.D.R. PART - A (2020)

NURI CHWOK SH -63 TO AZAM NAGAR

DETAILED ESTIMATE OF F.D.R. REPAIRING ROAD

ROAD LENGTH	0 TO 2783		
DISTRICT	KISHANGANJ		
BLOCK	THAKURGANJ		
DIVISION	KISHANGANJ - 2		
TOTAL LENGTH OF ROAD	2.783		KM
TOTAL COST OF F.D.R. PART - A	26.09 Rs. 52.191		Lacs
ADD G.S.T @ 12%	Rs. 6.263		Lacs
Add Seigniorage Fee @ 10 %	0.775 Rs. 1.541		Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 29.995		Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Kishanganj - 2

Inspection Report for flood damage work

Date: 11.12.2020

1. Name of PIUs- E. E. RWD (works) Division Kishanganj - 2

2. Name of Block/Road- Nuri ~~chowk~~ chowk SH-63 to Azamnagar

A. For Road

1. Damage Location/Chainage : 935 m

2. Damage Length : 114.9 m

3. Nature of Damage : Bank cutting & ditch

4. Details of Restoration :

i Material being used in Restoration

: Local sand, Brick Bats, H-Pipe

ii Equipment/Tools being used in Restoration works:

Tractor

iii Procedure taken up in Restoration works :

iv Restored Length

: 114.9 m

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

:

ii Equipment/Tools being used in Restoration works:

:


iii Procedure taken up in Restoration works


:

iv Restored Length

:


N/A


Signature of JE/AE/EE


11/12/2020
AE



12/12/20


Signature

(Name of Inspector)

TECHNICAL REPORT

Name of Work - FDR To Road From... Nuri Chowk SH-63 to Azam Nagar.
Head - FDR
Estimated cost - 99.995... Lacs


The work done estimate has been framed for the restoration (motorable) of traffic for the above road which was damage during the year 2020-2021 flash flood.


(A) Source of materials


Brick Bats - Local Kiln
Fine sand - Local
Cement Bag - Local Market
Aggregate for G.S.B - Matigara (Silliguri) by road up to site.
Bamboo - Local
Earth - Private land from 1000m lead.

(B) Rate - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.

Sanction of estimate is much needed for payment of the work which was already done.


J.E.
R.W.D
Kishanganj-2


A.E.
R.W.D
Kishanganj-2


E.E.
R.W.D
Kishanganj-2

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : NURI CHWOK SH -63 TO AZAM NAGAR
 DISTRICT KISHANGANJ
 DIVISION KISHANGANJ - 2
 BLOCK THAKURGANJ
 LENGTH OF ROAD (IN KM) 2.783

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK Local sand	28.138
2	BRICK BAT	22.591
3	G.S.B.	0.000
4	SAND BAG	0.000
5	BAMBOO WORK	1.463
4	HUME PIPE	0.000
TOTAL COST OF PROJECT =		52.191
Add G.S.T. @ 12%		6.263
Add Seigniorage Fee @ 10 %		1.541
Total Cost of Restoration Work =		59.995

29.995

[Signature]
 JE
 RWD

[Signature]
 AE
 RWD

[Signature]
 EE
 RWD

Technically Approved for Rs. ~~52.191~~ 59.995 Lacs (Twenty nine Lacs ninety nine thousand five hundred) only.

[Signature]
 अधीक्षण अभियन्ता
 ग्रामीण कार्य विभाग
 कार्य अंचल, किशनगंज