



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR REPAIRING OF ROAD

F.D.R. PART - A (2020)

PWD ROAD TO DUMARIA

DETAILED ESTIMATE OF F.D.R. REPAIRING ROAD

ROAD LENGTH	0 TO 1534	
DISTRICT	KISHANGANJ	
BLOCK	THAKURGANJ	
DIVISION	KISHANGANJ -2	
TOTAL LENGTH OF ROAD	1.534	KM
TOTAL COST OF F.D.R. PART - A	^{20.20} Rs. 72,504-	Lacs
ADD G.S.T @ 12%	^{2.62} Rs. 8,700-	Lacs
Add Seigniorage Fee @ 10 %	Rs. 4,972- 0.552	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	^{23.176} Rs. 83,176	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Kishanganj - 2

Inspection Report for flood damage work

Date: 11.12.2020

1. Name of PIUs- E. E. RWD (works) Division Kishanganj-2

2. Name of Block/Road- Takurganj / PWD Road to Dumarua

A. For Road

1. Damage Location/Chainage : 1080 m & 1487 m

2. Damage Length : 427 m

3. Nature of Damage : Ditch & flank cutting

4. Details of Restoration :

i Material being used in Restoration ~~local sand~~ : Local sand, Bombr, Brick Bats etc.

ii Equipment/Tools being used in Restoration works: Tractor and Roller

iii Procedure taken up in Restoration works :

iv Restored Length : 427 m

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :


iv Restored Length :

Signature of JE/AE/EE


11/12/2020
AE



12/12/20



Signature

(Name of Inspector)

TECHNICAL REPORT

Name of Work - FDR To Road From PWD Road to Dumariya.
Head - FDR 23.176 2
Estimated cost - 83.176 Lacs

The work done estimate has been framed for the restoration (motarable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

(A) Source of materials

Brick Bats - Local Kiln
Fine sand - Local
Cement Bag - Local Market
Aggregate for G.S.B - Matigara (Silliguri) by road up to site.
Bamboo - Local
Earth - Private land from 1000m lead.

(B) Rate - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.

Sanction of estimate is much needed for payment of the work which was already done.

Arjun
11/12/20
J.E
R.W.D
Kishanganj-2

Arjun
11/12/20
A.E
R.W.D
Kishanganj-2

Arjun
11/12/20
E.E
R.W.D
Kishanganj-2

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : PWD ROAD TO DUMARIA
DISTRICT KISHANGANJ
DIVISION KISHANGANJ -2
BLOCK THAKURGANJ
LENGTH OF ROAD (IN KM) 1.534

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	23.500
2	BRICK BAT	26.865
3	G.S.B.	0.000
4	SAND BAG	20.762
5	BAMBOO WORK	1.377
4	HUME PIPE	0.000
TOTAL COST OF PROJECT =		22.604 20.20
Add G.S.T. @ 12%		8.7 → 2.40
Add Seigniorage Fee @ 10 %		1.972 → 0.552
Total Cost of Restoration Work =		83.476 23.176

[Signature]
JE
RWD

[Signature]
AE
RWD

[Signature]
EB
RWD

Technically Approved for Rs. ~~Eighty~~ ^{Twenty} 3.176 Lacs (three Lacs seventeen thousand six hundred) only.

[Signature]
अधीक्षण अभियन्ता
ग्रामीण कार्य विभाग
कार्य अंचल, किशनगंज