



# ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

## DETAILED PROJECT REPORT FOR REPAIRING OF ROAD

F.D.R. PART - A (2020)

L028 CHEGA GHAT TO HAROBHITTA

### DETAILED ESTIMATE OF F.D.R. REPAIRING ROAD

ROAD LENGTH	0 TO 2000	
DISTRICT	KISHANGANJ	
BLOCK	THAKURGANJ	
DIVISION	KISHANGANJ - 2	
TOTAL LENGTH OF ROAD	2.000	KM
TOTAL COST OF F.D.R. PART - A	Rs. <sup>25.033</sup> <del>42.093</del>	Lacs
ADD G.S.T @ 12%	Rs. <sup>3.00</sup> <del>5.051</del>	Lacs
Add Seigniorage Fee @ 10 %	Rs. <sup>1.31</sup> <del>2.202</del>	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. <sup>29.347</sup> <del>49.347</del>	Lacs

SUBMITTED BY  
The Executive Engineer,  
Works Division, Kishanganj - 2

## Inspection Report for flood damage work

Date: 11.12.2020

1. Name of PIUs- Executive Engineer Rural works department work division  
Kishanganj - 2
2. Name of Block/Road- Thakurganj / 2028 chaje ghat to Harobhilla.


### **A. For Road**

1. Damage Location/Chainage : 900 m
2. Damage Length : 131.9 m
3. Nature of Damage : ditch and flank cutting.
4. Details of Restoration :
- i Material being used in Restoration : Tractor  
Local Sand, Brick bat, Humepipe.
  - ii Equipment/Tools being used in Restoration works: Tractor.
  - iii Procedure taken up in Restoration works :
  - iv Restored Length : 131.9 m.

### **B. For Bridge**


1. Damage Location/Chainage :
2. Damage Length :
3. Nature of Damage :
4. Details of Restoration :
- i Material being used in Restoration :
  - ii Equipment/Tools being used in Restoration works:
  - iii Procedure taken up in Restoration works :
  - iv Restored Length :

NA

  
Signature of JE/AE/EE

  
11/12/20  
AE

  
11/12/20

  
Signature  
(Name of Inspector)

## TECHNICAL REPORT

Name of Work - FDR To Road From. L028. Chega ghat to Harobhi Ha  
Head - FDR 29.347  
Estimated cost - 49.347 Lacs

The work done estimate has been framed for the restoration (motorable) of traffic for the above road which was damage during the year 2020-2021 flash flood.

### (A) Source of materials

Brick Bats - Local Kiln

Fine sand - Local

Cement Bag - Local Market

Aggregate for G.S.B - Matigara (Silliguri) by road up to site.

Bamboo - Local

Earth - Private land from 1000m lead.

(B) Rate - Carriage has been analyzed on minimum lead. Finished rate has been calculated without contractor's profit on MORD norms. Carriage of materials has been added to finished rate. Basic Rates are evaluated from rates approved by State schedule rate committee. 12% GST & 1% Labour cess has been added in the estimate in abstract part.

Sanction of estimate is much needed for payment of the work which was already done.

Ayngv.  
11/12/20  
J.E  
R.W.D  
Kishanganj-2

Aul  
11/12/20  
A.E  
R.W.D  
Kishanganj-2

R.P.  
12/12/20  
E.E  
R.W.D  
Kishanganj-2



**GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD**

NAME OF ROAD : L028 CHEGA GHAT TO HAROBHITTA  
DISTRICT KISHANGANJ  
DIVISION KISHANGANJ - 2  
BLOCK THAKURGANJ  
LENGTH OF ROAD (IN KM) 2.000

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK <i>Local Sand.</i>	9.584
2	BRICK BAT	31.459
3	G.S.B.	0.000
4	SAND BAG	0.000
5	BAMBOO WORK	0.000
4	HUME PIPE	1.050
TOTAL COST OF PROJECT =		42.093 25.033
Add G.S.T. @ 12%		5.051 3.00
Add Seigniorage Fee @ 10 %		2.202 1.31
Total Cost of Restoration Work =		49.347 29.347

*[Signature]*  
JE  
RWD

*[Signature]*  
11/12/2020  
AE  
RWD

*[Signature]*  
11/12/2020  
JE  
RWD

Technically Approved for Rs. *29.347* Lacs. (*Twenty nine Lacs thirty four thousand seven hundred*) only.

*[Signature]*  
20/11/20  
अधीक्षण अभियन्ता  
ग्रामीण कार्य विभाग  
कार्य अंचल, किशनगंज