

(4)

RURAL WORKS DEPARTMENT GOVT OF BIHAR



Name Of Work : Parmanandpur-Parari

BLOCK

DUMRA

FDR

Rs. ~~1149507.00~~

1103484 = 00

Year - 2020-21

NAME OF CIRCLE - R.W.D., WORKS CIRCLE, SITAMARHI

NAME OF DIVISION - R.W.D., (W) DIVISION, SITAMARHI

प्रतिवेदन

कार्य का नाम :- परमानन्दपुरी चररी पथ में

बाढ़ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।

प्राक्कलित राशि:- ₹ 1103484 = 00

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार, पटना के पत्रांक 1103484 दिनांक 11/03/21 के अनुपालन में उक्त पथ के कार्य का प्राक्कलन तैयार किया गया है।

संलग्न प्राक्कलन 2020 के जुलाई माह में ₹ 1103484 प्रखंड में आई मीषण बाढ़/अतिवृष्टि से क्षतिग्रस्त परमानन्दपुरी चररी पथ में बाढ़ क्षतिग्रस्त मरम्मति मद से यातायात चालू करने हेतु तैयार किया गया है जिसकी प्राक्कलित लागत Rs. 1103484 = 00 है, उक्त पथ का निर्माण PMGSY/MMGSY/NABARD/GTSNY/SCP/MNP/MR योजनान्तर्गत हुआ है एवं योजना अनुरक्षण अवधि में है/नहीं है।

पथ के कटे (क्षतिग्रस्त) भाग में आवश्यकता अनुसार Brick-bats, Rabbish भरकर MT Sand Bag, बास बल्ला चचरी एवं लोकल बालू का प्रावधान किया गया है ताकि यातायात चालू हो सकें।

प्राक्कलन के मदों का दर वर्तमान अनुसूचित दर से लिया गया है।

11/03/21

कनीय अभियंता
ग्रामीण कार्य विभाग,
प्रशाखा परमानन्दपुरी

11/03/21

सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमंडल परमानन्दपुरी।

11/03/21

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग, कार्य
कार्य प्रमंडल सीतामढ़ी।

DETAILED ESTIMATE FOR F.D.R.

General Abstract of Cost

Name of Road : Parmanandpur-Parari
Length of Road : 0.0 KM
Block : DUMRA
DISTRICT : SITAMARHI

S.No.	Particulars	Total Cost (in Lakh)
1	Total Cost for Motorable Roads	1017263.00 976535=00
2	Labour cess @1%	10172.83 9765=00
3	GST @12%	122071.56 117184=00
	Total Cost of Road Repair	1149507.19
	Say	1149507.00

1103484=00

eh
04/01/21
JE

h
04/01/2021
AE

1103484=00
EE

EE pupri wari 5A 244
10/2/21

हुआतुआतु B. 09/5/21 को बनेको-

वार्ड.
02/02
15.4.21.
AB

1103484=00

T/A is accorded for Rs. ~~1149507=00~~ (Rupees eleven lakh
fourty nine thousand ~~five~~ hundred ~~seven~~ only)
three four eighty four

SP
10/5/21

S.E
Road, Sitamarshi

Schedule of Quantity

Name Of Work : Parmanandpur-Parari

Block DUMRA

S.No	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	OF ITEMS Sand Filling in Foundation Trenches as per Drawing & Technical Specification.	0.00	Cum	401.00	0.00
2	Providing and laying of Brick bat obtained from chimney with machanical means with all spreading, grading to required slope and compacted at OMC to acheive required density with all complete as per the direction of engineer in charge.	724.38 704.98			0.00
	Less 20% for Voids	146.88 141.00			
		587.50 563.98	Cum	1546.00	908281.18 871913.00
3	Single bamboo palasiding / walling of whole 2nd class bamboo (Jati or Bethua) 75mm dia and closely packed & driven including fitting fixing with half bamboo kamis horizontally in three rows with cane or tying with wire complete and struts 1.5 m apart longitudinally and providing brush wood as per drawing and technical specifications Clause 1302.5	0.00	m	172.62	0.00
4	Providing ,laying and placing empty cement bag filled with local sand including stitching with sutali etc. ----- do - ----- do-----all complete job as per specification and direction of E/I.(Including Royalty and all Taxes)	0.00	no.	23.12	0.00
5	Providing and Laying Reinforced Cement Concrete Pipe NP3 as per design in Single Row with old available pipe	0.00	m	3158.69	0.00
6	Providing Quarry Material Rabbish for filling the voids in bricks bats -----do----- all complete job as per specification and direction of E/I.				
	Taking 20% of Brick Qty for Rabbish	146.88 141.00	Cum	742.00	104622.00 108981.39

Total

Say

~~1017262.57~~

~~1017263.00~~

976535.00

eh
04/01/21
JE

h
04/01/21
AE

h
04/01/21
EE

Details of Measurement of ditches filled by brick bats and rabbish

Name Of Work : Parmanandpur-Parari					L	W	H	VOLUME
					30.00	4.20	0.95	119.70
					30.00	4.20	0.95	119.70
					20.00	4.20	1.05	88.20
					20.00	4.25	1.05	89.25
					9.00	3.80	0.90	30.78
					10.00	4.80	1.90	91.20
					10.00	4.90	2.20 1.60	107.80 78.40
					15.00	3.90	1.50	87.75
					Total (in Cum)			734.38

704.98

eh
04/01/21
nt

h
04/01/2021
nt

h
4/1/21

Samir
22-1-21