

**RURAL WORKS DEPARTMENT**  
**GOVT OF BIHAR**



Name Of Work : L095-Sahiyara Police Station To Katahi  
Chamar Tola (VR54)

BLOCK

Bathnaha

**FDR**

Rs. 76526.00

Year - 2020-21

NAME OF CIRCLE - R.W.D., WORKS CIRCLE, SITAMARHI

NAME OF DIVISION - R.W.D., (W) DIVISION, SITAMARHI

**DETAILED ESTIMATE FOR F.D.R.**

**General Abstract of Cost**

Name of Road : L095-Sahiyara Police Station To Katahi Chamar Tola (VR54)  
 Length of Road : 0.0 KM 2.808 KM  
 Block : Bathnaha  
 DISTRICT : SITAMARHI

S.No.	Particulars	Total Cost (in Lakh)
1	Total Cost for Motorable Roads	67722.00
2	Labour cess @1%	677.22
3	GST @12%	8126.64
	Total Cost of Road Repair	76525.86
	Say	76526.00

*[Signature]*  
26/12/20  
JE

*[Signature]*  
26/12/2020  
AE

*[Signature]*  
4/1/21  
EE

verify.  
Rk for  
13.1.21  
AP2

*[Signature]*  
22/1/21

Technically Approval for Rs - 76526 = 00 (Rupees seventy six thousand five hundred twenty six) only.

EE Pukri का जोर

प्रतिवेदन 244 दिनांक - 10/02/21

सुधारोपरान्त - दिनांक - 09/05/21 उपलब्ध

*[Signature]*  
10/5/21  
Superintending Engineer  
Rural Works Department  
Works Circle, Sitamarhi



### Schedule of Quantity

Name Of Work : L095-Sahiyara Police Station To Katahi Chamar Tola (VR Block Bathnaha

S.No	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<b>OF ITEMS</b>				
1	Sand Filling in Foundation Trenches as per Drawing & Technical Specification.	0.00	Cum	401.00	0.00
2	Providing and laying of Brick bat obtained from chimney with machanical means with all spreading, grading to required slope and compacted at OMC to acheive required density with all complete as per the direction of engineer in charge.	48.89			0.00
	Less 20% for Voids	-9.78			
		39.11	Cum	1546.00	60467.15
3	Single bamboo palasiding / walling of whole 2nd class bamboo (Jati or Bethua) 75mm dia and closely packed & driven including fitting fixing with half bamboo kamis horizontally in three rows with cane or tying with wire complete and struts 1.5 m apart longitudinally and providing brush wood as per drawing and technical specifications Clause 1302.5	0.00	m	172.62	0.00
4	Providing ,laying and placing empty cement bag filled with local sand including stiching with sutali etc. ----- do ----- do-----all complete job as per specification and direction of E/I.( Including Royalty and all Taxes)	0.00	no.	23.12	0.00
5	Providing and Laying Reinforced Cement Concrete Pipe NP3 as per design in Single Row with old available pipe	0.00	m	3158.69	0.00
6	Providing Quarry Material Rabbish for filling the voids in bricks bats -----do----- all complete job as per specification and direction of E/I.				
	Taking 20% of Brick Qty for Rabbish	9.78	Cum	742.00	7255.24

Total 67722.39

Say 67722.00

*T. S.*  
26/12/20  
JE

*S. S.*  
26/12/20  
AE

*W. S.*  
4/1/21  
EE

**Details of Measurement of ditches filled by brick bats and rabbish**

Name Of Work : L095-Sahiyara Police Station To Katahl Chamar Tola (VR54)

	L	W	H	VOLUME
	7.50	$(4.50+3.20)/2$	1.50	43.31
	4.00	$(2.00+1.10)/2$	0.90	5.58
	Total (in Cum)			48.89

LAYING HUME PIPE OF 1000 mm dia	0	2	2.5	0.000
---------------------------------	---	---	-----	-------

Cement Bage				0
-------------	--	--	--	---

T-42  
26/12/20

*[Signature]*  
26/12/2020  
AE

*[Signature]*  
4/1/21



## प्रतिवेदन

कार्य का नाम :- 4095 Sahiyara Police Station to Kathi Chamas tola पथ में  
बाढ़ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।


प्राक्कलित राशि:- Rs. 76526 = 10


अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार, पटना के पत्रांक दिनांक .....  
के अनुपालन में उक्त पथ के कार्य का प्राक्कलन तैयार किया गया है।


संलग्न प्राक्कलन 2020 के जुलाई माह में 92101ET प्रखंड में आई भीषण बाढ़ से  
क्षतिग्रस्त 4095 Sahiyara Police Station to Kathi Chamas tola पथ  
में बाढ़ क्षतिग्रस्त मरम्मत मद से यातायात चालू  
करने हेतु तैयार किया गया है जिसकी प्राक्कलित लागत Rs. 76526 है, उक्त  
पथ का निर्माण PMGSY/MMGSY/NABARD/GTSNY/SCP/MNP/MR  
योजनान्तर्गत हुआ है एवं योजना अनुरक्षण अवधि में हैं/नहीं हैं।

पथ के कटे (क्षतिग्रस्त) भाग में आवश्यकता अनुसार Brick-bats, Rabbish भरकर MT  
Sand Bag, बास बल्ला चचरी एवं लोकल बालू का प्राक्धान किया गया है ताकि यातायात  
चालू हो सकें।

प्राक्कलन के मदों का दर बर्तमान अनुसूचित दर से लिया गया है।

  
कनीय अभियंता  
ग्रामीण कार्य विभाग,  
प्रशाखा 92101ET

  
सहायक अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य अवर प्रमंडल 92101ET

  
कार्यपालक अभियंता,  
ग्रामीण कार्य विभाग, कार्य  
कार्य प्रमंडल सीतामढ़ी।