

RURAL WORKS DEPARTMENT GOVT OF BIHAR



Name Of Work : रनौली से दिघी

BLOCK

Bathnaha

FDR

660749.00
Rs. ~~700664~~.00

Year - 2020-21

NAME OF CIRCLE - R.W.D., WORKS CIRCLE, SITAMARHI

NAME OF DIVISION - R.W.D., (W) DIVISION, SITAMARHI

DETAILED ESTIMATE FOR F.D.R.

General Abstract of Cost

Name of Road : रनौली से दिघौ
Length of Road : 0.0 KM 4.7
Block : Bathnaha
DISTRICT : SITAMARHI

S.No.	Particulars	Total Cost (in Lakh)
1	Total Cost for Motorable Roads	584734.00 620057.00
2	Labour cess @1%	5847.34 6200.57
3	GST @12%	70168.08 74406.84
	Total Cost of Road Repair	660749.42 700664.41
	Say	660749.00 700664.00

JE 26/12/20

AE 26/12/20

EE 4/1/21

verified.
RKD
13.1.21
AB

660749-
22/1/21

Technically approval for Rs. 660749-00 (Rupees Six lac
Sixty thousand seven hundred forty nine) only.

EE Pukri काजी

प्रतिवेदन 244 दिनांक- 10/04/21

सुधारोपरान्त दिनांक- 09/05/21 को उपलब्ध

Superintending Engineer
Rural Works Department
Works Circle, Sitamarhi


Schedule of Quantity


Name Of Work : रनीली स दिंधी


Block Bathnaha

S.No	OF ITEMS	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1		Sand Filling in Foundation Trenches as per Drawing & Technical Specification.	0.00	Cum	401.00	0.00
2		Providing and laying of Brick bat obtained from chimney with machanical means with all spreading, grading to required slope and compacted at OMC to achelve required density with all complete as per the direction of engineer in charge.	422.13 447.63			0.00
		Less 20% for Voids	84.43 89.53			
			337.70 358.10	Cum	1546.00	552090.38 553628.78
3		Single bamboo palasiding / walling of whole 2nd class bamboo (Jati or Bethua) 75mm dia and closely packed & driven including fitting fixing with half bamboo kamis horizontally in three rows with cane or tying with wire complete and struts 1.5 m apart longitudinally and providing brush wood as per drawing and technical specifications Clause 1302.5	0.00	m	172.62	0.00
4		Providing ,laying and placing empty cement bag filled with local sand including stiching with sutali etc. ----- do ----- do-----all complete job as per specification and direction of E/I.(Including Royalty and all Taxes)	0.00	no.	23.12	0.00
5		Providing and Laying Reinforced Cement Concrete Pipe NP3 as per design in Single Row with old available pipe	0.00	m	3158.69	0.00
6		Providing Quarry Material Rabbish for filling the voids in bricks bats -----do----- all complete job as per specification and direction of E/I.				
		Taking 20% of Brick Qty for Rabbish	84.43 89.53	Cum	742.00	62643.75 66427.92

Total ~~620056.71~~ 584734.13
Say ~~620057.00~~ 584734.00


JE


AE


EE

Details of Measurement of ditches filled by brick bats and rabbish

Name Of Work : रनौली से दिघी					L	W	H	VOLUME
					30.00	$(1.90+2.20)/2$	$(0.40+0.60)/2$	30.75
					30.00	2.15	$(0.50+0.40)/2$	29.03
				Ditch below GL	3.00	2.50	0.60	4.50
					3.00	2.50	0.60	4.50
					8.00	$(4.50+3.50)/2$	1.10	35.20
					30.00	$(4.00+4.50)/2$	0.90 0.70	114.75 89.25
					25.00	4.00	$(0.60+0.70)/2$	65.00
					20.00	$(3.50+3.80)/2$	$(0.90+0.60)/2$	54.75
					27.80	$(3.60+2.90)/2$	0.90	81.32
					12.00	$(3.30+2.50)/2$	0.80	27.84
					Total (in Cum)			447.63 422.13

12/12/20
26/12/20
JE

26/12/2020
AE

4/1/21

प्रतिवेदन

कार्य का नाम :- रौली से दिग्दी पथ में

बाढ़ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।

प्राक्कलित राशि:- ^{660749.00}
~~Rs 700664.00~~

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार, पटना के पत्रांक..... दिनांक.....
के अनुपालन में उक्त पथ के कार्य का प्राक्कलन तैयार किया गया है।

संलग्न प्राक्कलन 2020 के जुलाई माह में प्रस्तावित प्रखंड में आई भीषण बाढ़ से
क्षतिग्रस्त रौली से दिग्दी पथ
में बाढ़ क्षतिग्रस्त मरम्मति मद से यातायात चालू
करने हेतु तैयार किया गया है जिसकी प्राक्कलित लागत Rs. ^{660749.00}
~~700664.00~~ हैं, उक्त
पथ का निर्माण PMGSY/MMGSY/NABARD/GTSNY/SCP/MNP/MR
योजनान्तर्गत हुआ है एवं योजना अनुरक्षण अवधि में हैं/नहीं हैं।

पथ के कटे (क्षतिग्रस्त) भाग में आवश्यकता अनुसार Brick-bats, Rabbish भरकर MT
Sand Bag, बास बल्ला चचरी एवं लोकल बालू का प्रावधान किया गया है ताकि यातायात
चालू हो सकें।

प्राक्कलन के मदों का दर वर्तमान अनुसूचित दर से लिया गया है।

26/12/20
कनीय अभियंता
ग्रामीण कार्य विभाग,
प्रशाखा...प्रस्तावित...

26/12/2020
सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमंडल...प्रस्तावित...

4/1/21
कार्यपालक अभियंता,
ग्रामीण कार्य विभाग, कार्य
कार्य प्रमंडल सीतामढ़ी।