

ABSTRACT

Road name - Temporary Restoration of Road from REO road to Gausadih

Block-DARBHANGA

RWD (W) DIVISION DARBHANGA -1

Road Actual Length - 1.00 KM

Effectuated Road Length 111.80 M.

S.No.	ITEM	UNIT	QUANTITY	RATE	AMOUNT (Rs)
1	Providing and filling bricks bats in ditches including cost of bricks bats and labour all complete job as per specification and direction of E/I.	CUM	236.783	1867.76	442254
	Add G.S.T. 12 %				53070
	Add 1 % Labor cess				4423
	Seigniorage Fee @1063.00/cum x0.10				25170
	Total				524917 ✓

[Signature]
J.E.

Work Section Darbhanga-2

[Signature]
A.E.

Work Sub-Division
Darbhanga

[Signature]
E.E.

RWD Darbhanga -1

Total Rs. 5,24,917=00

कार्यपालक अभियंता, आगार वि०, कार्यप्रमंडल-कुलपराय का पत्र:- 542 अंश
दिनांक:- 07/04/2021 के द्वारा सुपति- जाँच प्रतिवेदन के आधार पर—

Post-fee to T/A Rs 5,24,917=00 (Rupees Five Lacs—
—twenty four thousand nine hundred seventeen) only.

[Signature]
09.04.21
Superintending Engineer
RWD, Works Circle, Darbhanga
09/04/2021

Detailed Estimate for Temporary Restoration of REO road to Gausadih road for the year 2020 -21.

Block -Darbhanga

Total Restoration Length -111.80 M

R.W.D.[W] Division -Darbhanga -1

Length -1.00 km

S.N.	item	No.	Length (M)	Width(M)	Depth (M)(AV)	Quantity (cum)
1	Providing and filling bricks bats in ditches including cost of bricks bats and labour all complete job as per specification and direction of E/I .					
	Chainage in M					
	0	1	12.00	(7.50+4.75)/2	1.250	91.875
		1	10.00	(4.00+4.80)/2	0.600	26.400
		1	4.80	1.50	0.300	2.160
	70	1	1.00	0.90	0.150	0.135
		1	1.60	0.60	0.150	0.144
		1	3.00	1.00	0.200	0.600
	294	1	61.00	3.20	(0.45+0.60)/2	102.480
		1	3.10	1.25	0.300	1.163
		1	3.10	1.25	0.225	0.872
	Branch road at 112 M	1	4.50	1.25	0.225	1.266
		1	2.60	1.00	0.200	0.520
	180	1	2.10	2.25	0.750	3.544
	188	1	3.00	2.50	0.750	5.625
	Total Qty.					236.783 ✓

[Signature]
28/12/20

J.E.

[Signature]
28/12/20

A.E.

[Signature]

E.E.

RWD(W) Division Darbhanga -1