

ABSTRACT

Road name - Temporary Restoration of Road from Panta To Shahzadpur

Block-DARBHANGA

RWD (W) DIVISION DARBHANGA -1

Road Actual Length - 3.45KM

Efected Road Length 336.15 M.

S.No.	ITEM	UNIT	QUANTITY	RATE	AMOUNT (Rs)
1	Providing and filling bricks bats in ditches including cost of bricks bats and labour all complete job as per specification and direction of E/I.		810.274		11398832
		CUM	651.127	1867.76	1216149
	Add G.S.T. 12 %				145938
	Add 1 % Labor cess				12161
	Seigniorage Fee				69215
	Total				1443463

13678620
1139920
8487420
135294220

Rs-13,52,942=

[Signature]
S.E.

Work Section Darbhanga-2

[Signature]
A.E.

Work Sub-Division
Darbhanga

[Signature]
E.E.

RWD Darbhanga -1

कार्यपालन अभियंता द्वारा कां वि० कार्यप्रमाणपत्र फुलपरास के पत्रांक 542 अनु० दिनांक 07/04/2021 के द्वारा समाप्त जॉय प्रतिक्रिये के आधार पर—

Post-Facto T/A for Rs-13,52,942= (Rupees- Thirteen Lacs fifty two Thousand nine hundred forty two) only

Superintending Engineer

RWD, Works Circle, Darbhanga

09/04/2021

Detailed Estimate for Temporary Restoration Of Panta to Shahzadpur road for the year 2020 -21.

Block -Darbhanga

R.W.D.[W] Division -Darbhanga -1

Total Restoration Length -336.15 M

Length -3.45 km

S.N.	item	No.	Length (M)	Width(M)	Depth (M)	Quantity (cum)
1	Providing and filling bricks bats in ditches including cost of bricks bats and labour all complete job as per specification and direction of E/I .					
	CH-1525 M	1	4.10	1.20	0.225	1.107
		1	1.25	1.10	0.225	0.309
		1	1.00	1.10	0.150	0.165
	CH- 1530 M	1	5.00	1.10	0.225	1.238
		1	7.20	1.10	0.300	2.376
		1	1.10	1.10	0.150	0.182
	CH- 1700 M	1	35.7	2.25	(0.450+0.60)/2	42.171
	CH- 1810 M	1	8.20	2.10	0.300	5.166
		1	0.60	0.60	0.150	0.054
	CH- 1850 M	1	30.00	(3.70+4.50)/2	0.75	92.25
		1	23.80	(3.75+4.90)/2	0.90	92.64
	West Bridge approach	1	2.10	1.80	0.700	2.646
		1	2.80	1.60	0.900	4.032
	North Approach	1	8.70	(4.50+5.60)/2	1.200	52.722
		1	25.00	(3.75+4.20)/2	0.600	59.625
		1	7.00	3.70	0.450	11.655
		1	5.80	1.25	0.300	2.175
	CH- 2620 M	1	9.00	4.00	0.750	27.000
		1	6.20	0.90	0.200	1.116
		1	4.40	1.20	0.225	1.188
		1	2.60	3.70	0.450	4.329
		1	11.20	2.10	0.300	7.056
		1	1.10	1.00	0.200	0.220
	West approach of East Bridge					
		1	5.70	4.20	(0.30+0.70)/2	11.97
		1	1.50	(3.75+6.80)/2	(0.80+0.30)/2	4.352
	North	1	3.50	2.500	0.900	7.875
	South	1	4.70	2.200	1.100	11.374
		1	4.20	3.800	0.350	5.586
	CH- 2725 M	1	28.00	(4.50+5.50)/2	(0.60+1.50)/2	147.00
		2	4.00	0.90	0.225	1.620
	CH- 2820 M	1	3.70	0.75	0.300	0.833
	CH- 3170 M	1	48.00	3.70	0.225	39.960
	At end of road	1	29.00	1.40	0.225	9.135
	TOTAL QTY .					651.127

J.E.

A.E.

E.E.

RWD(W) Division Darbhanga -1