

ABSTRACT

Road name - Temporary Restoration of Road from NH 57 Binod Yadav ke

Dukan se muslim tola Kakarghatti tak

Block-DARBHANGA

RWD (W) DIVISION DARBHANGA -1

Road Actual Length - 0.950 KM

Effectd Road Length 633.70 M.

S.No.	ITEM	UNIT	QUANTITY	RATE	AMOUNT (Rs)
1	Providing and filling bricks bats in ditches including cost of bricks bats and labour all complete job as per specification and direction of E/I.	CUM	888.866 922.448 955.266	1867.76	1660,188.00 1722,945.28 1784208
	Add G.S.T. 12 %			✓ 199,223.10	214105
	Add 1 % Labor cess			✓ 16602.40	17842
	Seigniorage Fee @1063.00/cum x0.10			✓ 94486.30	101545
	Total				2117699

[Signature]
J.E.

Work Section Darbhanga-2

[Signature]
A.E.

Work Sub-Division
Darbhanga

[Signature]
E.E.

RWD Darbhanga -1

कार्यवाला समित्या, 2170 का वि०, कार्यक्रम-कुलपति का पत्रिक 5/12 अक्टू/ दिनांक:-07/06/2021 के द्वारा स्थापित. लाय प्रविष्टि के आधार पर -

Post-fee to T/A Rs 19,70,499=00 (Rupees Nineteen lakhs - seventy thousand four hundred ninety nine) only.

[Signature]
09.04.21

Superintending Engineer
RWD, Works Circle, Darbhanga
09/04/2021

page no 10/02

Detailed Estimate for Temporary Restoration of N.H.57 Binod Yadav ke Dukan se muslim tola Kakarghatti tak road for the year 2020 -21.

Block -Darbhanga

Total Restoration Length -633.70 M

R.W.D.[W] Division -Darbhanga -1

Length -0.950 km

S.N.	item	No.	Length (M)	Width(M)	Depth (M)(AV)	Quantity (cum)
1	Providing and filling bricks bats in ditches including cost of bricks bats and labour all complete job as per specification and direction of E/I .					
	Chainage in M					
	0	1	16.00	0.60	0.600	5.760
	54 to 118	2	64.00	0.60	1.250	96.000
	118 to 137	1	19.00	0.70	1.300	17.290
		1	10.30	0.60	0.600	3.708
	137 to 165	2	28.00	0.75	1.200	50.400
	171 to 228	2	57.00	(0.60+1.10)/2	1.500	145.350 ✓
	R	1	13.00	(0.70+1.70)/2	1.500	23.400
	L	1	10.00	0.60	0.600	3.600
	269	2	28.00	(0.60+0.90)/2	0.600	25.200
	L	1	71.50	(0.75+1.20)/2	1.500	104.569 ✓
	340	1	70.00	0.60	1.000	42.000
		1	4.40	0.75	0.450	1.485
	344 L	1	6.50	0.60	0.300	1.170
	at 493 M towards river (chauk to north)	1	30.00	0.75	1.500	33.750
	344 to 372 R	1	28.00	(0.90+ ^{1.5} 2.50)/2	^{1.5} 2.00	50.40 95.200 ✓
	521 to 535	1	14.00	(0.90+3.00)/2	3.250	88.725 ✓
	560	1	12.00	(0.75+1.40)/2	1.200	15.480
		1	13.00	0.70	0.600	5.460
	578	1	16.00	(0.90+ ^{1.5} 2.25)/2	^{1.5} 2.000	28.80 50.400
	592	1	13.00	(0.75+1.50)/2	1.250	18.281 ✓
	593 L (Breach)	1	8.00	(3.50+5.50)/2	2.000	72.000
	600 R	1	60.00	0.60	0.750	27.000
	666	1	4.50	0.50	0.450	1.013
	691	1	9.00	3.50	0.450	14.175
	767 R	1	8.00	0.80	0.300	1.920
	790	1	10.50	0.90	1.000	9.450
		1	6.50	0.70	0.225	1.024

28/11/20

72

page no 02/02

lock -Darbhanga

L.W.D.[W] Division -Darbhanga -1

Total Restoration Length -633.70 M

Length -0.950 km

S.N.	item	No.	Length (M)	Width(M)	Depth (M)(AV)	Quantity (cum)
	885	1	3.50	(0.75+1.10)/2	0.450	1.457
	Total Qty.					955-266

~~922-466~~
888.866M³

JE
28/12/20

AE
28/12/20

E.E.

RWD(W) Division Darbhanga -1